

THE · W · A · SNOW IRON · WORKS



PRACTICAL STABLE FITTERS



19 · Portland · St · Boston · Mass.



Digitized by

The Association for Preservation Technology International

For the

Building Technology Heritage Library

<http://archive.org/details/buildingtechnologyheritagelibrary>

Stable Fittings

Snow's Sanitary Stall Floors

Cow Barn Fittings

Copper Weather Vanes



The W. A. Snow Iron Works

SALESROOM, 19 PORTLAND STREET, BOSTON

FACTORY AND WORKS, CHELSEA, MASS.

ESTABLISHED 1884

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

PRIVATE STABLE.



Interior of MR. H. H. ROGERS' STABLE, Fairhaven, Mass.

Fitted with Snow's Sanitary Stall Floors.

Mr. Charles Brigham, Architect.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

PRIVATE STABLE.



Interior of MR. E. C. SWIFT'S STABLE, Prides Crossing, Mass.

Fittings furnished by The W. A. Snow Iron Works.

Messrs. Little & Brown, Architects.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

PRIVATE STABLE.



Interior of MR. J. REED WHIPPLE'S STABLE, Lexington, Mass.

Fitted with Snow's Sanitary Stall Floors.

Mr. Charles Brigham, Architect.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

PRIVATE STABLE.



Interior of the Late HON. CHARLES F. SPRAGUE'S STABLE, Jamaica Plain, Mass.

Fittings furnished by The W. A. Snow Iron Works.

Messrs. Little & Brown, Architects.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

PRIVATE STABLE.



Interior of MR. HERBERT DUMARESQ'S STABLE, Chestnut Hill, Mass.

Fitted by The W. A. Snow Iron Works.

Messrs. Winslow & Bigelow, Architects.

PREFACE

IN issuing this Complete Catalogue of Stable Goods, great pains have been taken to illustrate the best methods of DRAINAGE and VENTILATION, and also to meet the wants of every class and design of stable, from the cheapest to the most elaborate. We have omitted many cuts of goods which have been published by other manufacturers (which have no place in modern stables) with the design of making ours as compact as possible.

We shall endeavor at all times to give our customers the benefit of our twenty years of practical experience in fitting up stables, among which are some of the best in the country. We can assure our clients that their outfit will be "Up to Date." We call special attention to our line of Fittings for Cow Barns, which are very complete.

We cheerfully send experienced men at all times to give practical information and take orders.

At our salesroom, 19 Portland Street, can be seen stalls fitted complete, with the latest improved fittings; these we shall be glad to show to any who may favor us with a call.

At our NEW FACTORY in Chelsea, Mass., we have added a large number of new machines, and are prepared to execute orders for Iron Stair Work, and all kinds of Wrought Iron and Copper Work, at lowest prices.

It will be our endeavor to ship all goods with promptness and despatch, and careful attention will be given to obtaining the lowest freight rates. We make our grateful acknowledgments to our customers and friends for past favors and trust to merit their future patronage.

Very respectfully,

THE W. A. SNOW IRON WORKS.

WILLIAM A. SNOW.

ALVAH W. CLARK.

November 1st, 1904.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.


SNOW'S SANITARY STALL FLOOR, 1904 PATTERN.

Over **9,000**
In Successful Use.

NINE POINTS why
you should use the
Snow Sanitary Stall
Floor:

Cleanliness.
Economy.
Healthfulness.
Neatness.
Comfort.
Humane.
Durability.
Simplicity.
Labor Saving.

SPECIAL.—We make
our basins with double
edge or flange when
called for.



Patented July 6, 1895.

PRICE LIST OF SINGLE STALLS.

No. 7G, 6 feet long by 2 feet, 6 inches wide,	\$18.00
" 8G, 6 " " " 3 " 0 " "	24.00
" 9G, 7 " " " 3 " 0 " "	32.00
" 10G, 6 " " " 4 " 6 " "	38.00

Box Stalls.

No. 11G, 6 feet long by 4 feet, 6 inches wide,	\$38.00
" 12G, 6 " " " 5 " 6 " "	46.00

What a floor consists of and what we send :

1. Heavy Cast Iron Stall Basin.
2. Rock maple floor over the basin, with heavy hinges, with brass pin, as shown in cut.
3. Improved Bell Trap Cesspool, with strainer 8 inches square.
4. Piece of Iron Soil Pipe, 18 inches long; 3-inch diameter, to connect with main soil pipe.
5. One pair of bridges for center of stall, to tie maple slats together to keep from warping.
6. One Stall Opener.
7. One Stall Cleaning Hook.

WHAT WE CLAIM.

Important Notice.—Things you should know about the Snow Sanitary Stall Floor.

The cost will be less in plumbing as our new outlet is used in connection with the floor, made so as to exclude short straws.

The large outlet to basin with our non-clogable strainer always insures perfect drainage.

Our hinges are entirely out of the way. There is no chance for the horse to chafe or injure himself in any way.

It is an absolutely Odorless Floor.

The convenient way of raising the floor in two parts.

One pail of water cleans the whole floor.

The outlet at the rear where it should be, makes it impossible to wash refuse past it.

The Cleaning Hook has a passage between the slats unobstructed by cleats, rods or hinges.

Our stall planks have a center tie or bridge which prevents them from warping sideways, without which it is IMPOSSIBLE TO DRAW A STALL CLEANING-HOOK, after being in use a few weeks.

The slatted floor opens at the center on hinges, which are on the extreme ends under the planks, and they offer no obstruction to a cleaning-hook.

This does away with all Nails, Screws and Hinges on top of Floor, and gives a horse a perfectly smooth and level floor to stand on, with no danger of stepping on anything that would cause him to slip or injure himself in any way.

The great saving in labor and bedding. ANY IMITATION OR INFRINGEMENT ON THIS PATENT WILL BE PROMPTLY PROSECUTED.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

SNOW'S SELF CLEANING STALL FLOOR, 1904 PATTERN.

With Reversible Slats, and arranged for Flushing Pipe.

Used in all the best Private Stables.

The Best on Earth.


The Snow Fittings are known to every horse-man.

The Floors can be taken out and dried with the bedding.

Absolutely Odorless.

Always clean and dry.

The Pan can be flushed out without lifting up the woods.



Patented July 6th, 1895.

Price List of Single Stalls.

No. 13G,	6 feet long by 2 feet, 6 inches wide,	\$22.00
" 14G,	6 " " " 3 " 0 " "	28.00
" 15G,	7 " " " 3 " 0 " "	36.00
" 16G,	6 " " " 4 " 6 " "	42.00

Box Stalls.

No. 17G,	6 feet long by 4 feet, 6 inches wide,	\$42.00
" 18G,	6 " " " 5 " 6 " "	50.00


By having reversible slats you get all the wear there is in the floor changing the woods from one side to the other also changing rear to front.

Our flushing arrangement will at once show its desirableness to every horseman as it will keep the stable much more sanitary, and does away with hose around the stall room.

The above prices include Heavy Cast Iron Pan Rock Maple Floor over Basin with heavy hinges, secured with heavy brass pins as shown in cut. Improved Bell Trap Strainer and Cesspool with Snow's Patent Outlet. Piece of Iron Soil Pipe, 18 inches long, 3 inches in diameter, to connect with Main Soil Pipe. One pair of bridges for center of stall to tie planks to prevent warping. One Stall Opener. One Stall Cleaning Hook.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

FRAMING PLAN, For Nos. 7G and 13G. When Floor Timbers run at right angle to Basins. Framing plans for other sizes of Floors sent on application.



STALL FLOOR FRAMING PLAN.

Scale $\frac{3}{8}$ -inch to one foot.


The Basin gets its bearing front and rear, consequently we have shown larger timbers at these points.

The Basin is placed 12 inches back from center of stall posts so as to provide for mares.

Sizes of timbers may be varied to suit the span. A special detailed framing plan will be sent on application.

Framing for Box Stall.—The BASIN for Box Stall should be placed in the center of Box Stall, getting its bearing on front and back timbers, same as in single stall.

Cut showing our Improved Stall Connection, non-clogable, made so as to exclude short straws and furnished with water seal 8 inches square.



PATENT PENDING.

Pipe outlet, 3-inch diameter.

Our Strainer and Bell Trap is the best in the market; it has no pocket to fill up with waste matter and is thus easily cleaned out.

Endorsed by All the Leading Plumbers.

Perfectly tight.

Is most easily connected, therefore the cheapest.


Where there are a large number of stalls the plumbers' charges are much less by using this connection.

The New Outlet connection between the stall basin and soil pipe consists of a pipe with a ring or collar around it. Made in any length, which is dropped into the outlet chamber and calked from the upper side, making an absolutely tight joint, and allowing plenty of head room for making connection with the main soil pipe under the stable.

It requires no rubber gasket, putty, etc., (which will corrode in a short time by the action of ammonia or salt;) it is calked the same way as any soil pipe making a lead joint.

NOTICE.—Be sure that the collar of the pipe rests on the bottom of the outlet chamber and that the end of the pipe does not ride on the hub of the soil pipe.

When the Timbers run Lengthways with the Basin.
Framing plans for other sizes of floors sent on application.




Special prices on this soil pipe made on application.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

SNOW'S SANITARY STALL FLOORS.

Used with Granolithic, Asphalt and Brick Floors.



Patented July 6, 1895.

We have had a large number of inquiries from our clients for a brick or cement floor for a stall who wish to have the horses stand on wood. To meet these requirements we have had the above floor constructed and it is being used with great success. The construction is similar to that for our wood floor, except it has a high flange all the way round it to the height of 3 inches. This is made so that in laying the cement or granolithic everything will come level and at the same time the edges of the granolithic will be kept from chipping.

The flanges at the sides make it perfectly tight as it allows it to break joints with no fear of leakage. The hinges are secured to the front and back of the basin with heavy brass screws.

Price List, Single Stalls.

No. 19G,	6 feet long by 2 feet, 6 inches wide,	\$24.00
" 20G,	6 " " 3 " 0 " "	28.00
" 21G,	7 " " 3 " 0 " "	32.00
" 22G,	7 " " 3 " 6 " "	42.00
" 23G,	7 " " 4 " 6 " "	48.00

Price List, Box Stalls.

No. 24G,	6 feet long by 5 feet, 0 inches wide,	\$48.00
" 25G,	7 " " 4 " 6 " "	48.00

The above prices include Heavy Cast Iron Pan, Rock Maple Floor over Basin with heavy hinges, secured with heavy brass screws as shown in cut. Improved Bell Trap Strainer and Cesspool with Snow's Patent Outlet. Piece of Iron Soil Pipe, 18 inches long, 3 inches in diameter, to connect with Main Soil Pipe. One pair of bridges for center of stall to tie planks to prevent warping. One Stall Opener. One Stall Cleaning Hook.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

SNOW'S SELF CLEANING STALL FLOOR, 1904 PATTERN.

With Reversible Slats and arranged for Flushing Pipe.

Used with Granolithic, Asphalt and Brick Floors.

The Best on Earth.


The Snow Fittings are known to every horseman.

The Floors can be taken out and dried with the bedding.

Absolutely Odorless.

Always clean and dry.

The Pan can be flushed out without lifting up the woods.



Patented July 6, 1895.

Price List, Single Stalls.

No.	26G,	6 feet long by 2 feet, 6 inches wide,	\$28.00
"	27G,	6 " " " 3 " 0 " "	32.00
"	28G,	7 " " " 3 " 0 " "	36.00
"	29G,	7 " " " 3 " 6 " "	46.00
"	30G,	7 " " " 4 " 6 " "	52.00

Price List, Box Stalls.

No.	31G,	6 feet long by 5 feet, 0 inches wide,	\$52.00
"	32G,	7 " " " 4 " 6 " "	52.00

By having reversible slats you get all the wear there is in the floor changing the woods from one side to the other also changing rear to front.

Our flushing arrangement will at once show its desirableness to every horseman as it will keep the stable much more sanitary, and does away with hose around the stall room.

The above prices include Heavy Cast Iron Pan, Rock Maple Floor over Basin with heavy hinges, secured with heavy brass pins as shown in cut. Improved Bell Trap Strainer and Cesspool with Snow's Patent Outlet. Piece of Iron Soil Pipe, 18 inches long, 3 inches in diameter, to connect with Main Soil Pipe. One pair of bridges for centre of stall to tie planks to prevent warping. One Stall Opener. One Stall Cleaning Hook.

The following up-to-date stables have in use the above floors.

LARZ ANDERSON, Washington, D. C.
E. C. SWIFT, Prides Crossing, Mass.
BRYCE J. ALLAN, Prides Crossing, Mass.
BAYARD THAYER, Lancaster, Mass.

WILLIAM F. BURDEN, Newport, R. I.
J. REED WHIPPLE, Lexington, Mass.
ROBERT G. SHAW, Wenham, Mass.
A. L. HOLLINGSWORTH, Milton, Mass.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.
--

The Snow Sanitary Stall Floor is known by all horsemen to be the Only Perfect System of Drainage.

Our unparalleled record of over **9,000** in constant use tells its own story.

STABLE DRAINAGE.

One of the most important features in the Stable is the Drainage.

Unless the stalls are properly drained you can never expect to find a healthful stable. No question concerning the plan of building a stable should have more careful thought than that of conducting the fluids from the building.

While from a sanitary standpoint the stable ought to be clean, the odors or gases which arise from the fluids injure the lungs and eyesight of the horses and also tarnish and spoil the finish of the carriages.

By the use of Snow's Sanitary Stall Floors the fluids run off directly into the sewer, leaving a dry and clean floor, assuring health and pure air.

Water-Tight Floors.

To Livery Stable men and all those who keep their horses on the second floor of the stable, or if one wishes to utilize his cellar for other purposes, the same question always arises—How am I to have a Water-Tight Floor? How am I to keep the fluids from coming down on nice carriages, and staining the ceiling of my otherwise very clean stable? This is a very important feature and no question should be more carefully considered.

We are prepared to lay complete, in connection with our SANITARY STALL FLOOR, guaranteed Water-Tight Floors. We make a specialty of this work, and will cheerfully give estimates for laying stable floors complete.

Examine our record. See if the floors we put down are not Water-Tight. Ask the owners about it.

If you are contemplating building a stable with a Water-Tight Floor, write to us, and we will give you references in your vicinity to look at and examine. We have put in more Water-Tight Floors in connection with our Sanitary Stall Floors than any other manufacturer.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

We take pleasure in making reference to the following, who have our floors in their stables:

Their endorsement of them is the best guarantee we can give.

William H. Moore, (Moore Bros.)	New York	F. A. Schermaron,	-	-	-	Lenox, Mass.
H. H. Rogers, (Standard Oil Co.,)	" "	Col. H. E. Smith,	-	-	-	Worcester, Mass.
George C. Boldt,	" "	Denman Thompson,	-	-	-	West Swansea, N. H.
Larz Anderson,	- - Washington, D. C.	A. N. Belding,	-	-	-	Rockville, Ct.
A. C. Burrage,	- - - - Boston	Norman B. Ream,	-	-	-	Thompson, Ct.
Eben D. Jordan,	- - - - "	P. A. B. Widener,	-	-	-	Ogontz, Pa.
Henry M. Whitney,	- - - - "	Joseph E. Widener,	-	-	-	" "
E. C. Swift,	- - - - "	Col. W. L. Elkins,	-	-	-	" "
J. Reed Whipple,	- - - - "	W. L. Elkins, Jr.,	-	-	-	" "
Bryce J. Allan,	- - - - "	Clement B. Newbold,	-	-	-	Jenkintown, "
Bayard Thayer,	- - - - "	James L. Blair,	-	-	-	St. Louis, Mo.
Fiske Warren,	- - - - "	W. D. Simmons,	-	-	-	" " "
H. H. Hunnewell,	- - - - Wellesley	C. L. Harrison,	-	-	-	Cincinnati, O.
Robert G. Shaw,	- - - - Boston	J. Dwight Lamb,	-	-	-	Clinton, Ia.
Henry P. King,	- - - - "	George A. Joselyn,	-	-	-	Omaha, Neb.
A. L. Hollingsworth,	- - - - "	E. A. Cudihy,	-	-	-	" "

LARGE STABLES FITTED WITH THE SNOW SANITARY STALL FLOOR:

Adams Express Co., New York,	-	70 Stalls	Johnson & Co., Boston,	-	-	-	65 Stalls
Adams Express Co., Boston,	-	65 "	F. H. & A. H. Chappell Co.,				
Riding Club, Ipswich St., Boston,	203	"	New London, Ct.,	-	-	-	43 "
Metropolitan Stable, Sears St., Boston,	190	"	H. E. Hall (Welch & Hall) Boston,	-	-	-	30 "
Vinals Stable, Endicott St., Boston,	206	"	A. Winter & Co., Bridgeport, Ct.,	-	-	-	21 "
Essex Stable, South St., Boston,	-	125 "	Scoville Mfg. Co., Waterbury, Ct.,	-	-	-	26 "
Henry C. Turner's Stable, Lawton St.,	146	"	Fall River Iron Works, Fall River, Mass.,	20	-	-	"
J. J. Short & Bros., Philadelphia,	-	115 "	Worcester Insane Asylum, Worcester,				
Acme Tea Co., Philadelphia,	-	66 "	Mass.,	-	-	-	10 "
F. Knight & Son, Corp., Boston,	-	67 "	Excelsior Stable, Manayunk, Pa.,	-	-	-	38 "

FIRE DEPARTMENTS:

Boston, Mass.,	Lawrence, Mass.,	Greenfield, Mass.,	Halifax, N. S.,
Fall River, Mass.,	Lowell, Mass.,	Providence, R. I.,	Poughkeepsie, N. Y.,
New Bedford, Mass.,	Leominster, Mass.,	Biddeford, Me.,	Yonkers, N. Y.,
Somerville, Mass.,	Winchester, "	Burlington, Vt.,	Superior, Wis.,
Chelsea, Mass.,	Watertown, "	Waterbury, Conn.,	West Superior, Wis.,
Everett, "	Peabody, Mass.,	Norwalk, Conn.,	Calumet, Mich.,
Beverly, "	Framingham, Mass.,	Norwich, "	Hancock, "
Newton, "	Dedham, Mass.,	New Haven, Conn.,	Marquette, Mich.,
Medford, "	Pepperell, "	Bridgeport, Conn.,	Cheyenne, Wyo.,
Milford, "	Natick, Mass.,	Meriden, Conn.,	Aspen, Col.
Hudson, "	Arlington, Mass.,		


CITIES HAVING IN USE THE SNOW SANITARY STALL FLOOR:

Boston, Mass., Water Department,	Boston, Mass., Street Department,	Quincy, Mass.,
Lawrence, Mass.,	Lowell, Mass.,	Medford, Mass.,
	Beverly, Mass.,	
	and Many Others.	

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

SNOW'S SANITARY MANGER.

This Manger is used when the horse is fed from the floor. **1,500 in use.**



Patented Dec. 29, 1896.


No. 33G.

The best on earth. Sells on sight. It has no equal. **Feeds Slowly.** Prevents all waste of grain. Prevents the horse eating too fast.

Price each complete, - - - - \$2.50

CORNER MANGER.

With Food Guard.



No. 36G.

Length on side, 14 1/2 inches; depth, 8 inches.


Price each, - - - - \$1.25

SNOW'S SANITARY MANGER.

Feeds Slowly.

This Manger is used when the horse is fed from the loft overhead.

This Manger is perfectly smooth inside and is easily cleaned out.



Patented Dec. 29, 1896.


It has no Partitions or Obstructions to injure the horses' mouths in any way, or break their teeth.

No. 34G, Manger, each, - - - \$2.00

" 35G, " with 9 feet of Grain Pipe and Hopper as shown, - - - 3.50

CORNER MANGER.

With wide Food Guard in Front.



No. 37G.

Length on side, 17 inches; depth, 10 inches.

Price each, - - - - \$1.50

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

ECONOMY FEED PIPE.


Every horse owner should have one. Feeds slowly.

The Economy Feed Pipe regulates the flow of oats, so that the horse has to feed slowly.

Horses are in much better shape after using the Economy Feed Pipe.

Can be used in feeding either from the floor or hay-loft, and are made to fit 2 1/2-inch Galvanized Iron Pipe.

They are also made adjustable so as to regulate the flow of grain and also to fit any Manger.



No. 38G.


No. 38G, price each, \$.60

CORNER MANGER, "The Hub." With Heavy Rolling Food Guard.




Length on side, 17 inches; depth, 10 inches.

No. 39G, price each, plain iron, - - \$2.00
" 40G, " " enameled, - - 6.50



View showing Economy Feed Pipe used with No. 37G Manger where galvanized grain chute and hopper is used to feed from above.

CORNER MANGER.



Length on side, 16 inches; depth, 9 1/2 inches.


No. 41G, price each, - - - - \$2.00

The above Manger has an Effectual Food Guard all around, preventing the horse wasting his oats.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

CORNER MANGER.

With Heavy Wide Food Guard.




No. 42G.

Length on side, 15 inches ; depth, 12 inches.
Price each, - - - - - \$2.50

SQUARE MANGER.


Designed especially for Wood Casing.



Length, 20 inches ; width, 14 inches ; depth, 9 inches.

No. 43G, price each,	-	-	-	-	\$2.00
" 44G, " " with inside Food	-	-	-	-	
Guard,	-	-	-	-	2.25

FIRE DEPARTMENT OR SIDE MANGER.




No. 45G, length, 24 inches ; width, 10 inches ; depth, 7 inches,	-	-	-	-	-	Price each, \$2.00
" 46G, " 17 " " 9 " " 7 "	-	-	-	-	-	" " 1.75
" 47G, " 17 " " 7 " " 7 "	-	-	-	-	-	" " 1.75

Any of these sizes made detachable at an extra cost each of \$1.50, also the above sizes made with rolling food guard to order at an extra cost each of 50 cents.


SIDE DETACHABLE MANGER.

Attachments are Flush.

SIDE MANGER.



Length, 18 inches ; depth, 8 inches ; width, 12 inches.
No. 48G, price each, - - - - - \$2.00
" 49G, " " with Food Guard, 2.25




Length, 18 inches ; depth, 8 inches ; width, 12 inches.
No. 50G, price each, - - - - - \$3.75
" 51G, " " with Food Guard, 4.00

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

CAST IRON MANGER AND WROUGHT IRON HAY RACK.

With Adjustable Extension Attachment at Ends.




No. 52G,	length, 4 feet 6 inches ;	width, 1 foot 11 inches,	-	-	-	-	-	-	Price each, \$18.50
" 53G,	" 5 "	width 1 foot 11 inches,	-	-	-	-	-	-	" " 21.00

Noiseless Hitch Weight, with Rollers and Leather Halter Strap, \$3.00 extra.

Any length furnished to order.

CAST IRON MANGER AND WROUGHT IRON HAY RACK.

With Adjustable Extension Attachment at Ends.




No. 54G,	length, 4 feet 6 inches ;	width, 1 foot 11 inches,	-	-	-	-	-	-	Price each, \$25.00
" 55G,	" 5 "	width, 1 foot 11 inches,	-	-	-	-	-	-	" " 27.00

Any length furnished to order.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

CAST IRON MANGER WITH WROUGHT IRON HAY RACK FOR BOX STALL.



No. 56G.

Left hand.


Length on back, 4 feet ; length on side, 2 feet 6 inches.

Price each, \$23.00

Inside dimensions of Manger, 16x16x12 inches deep.

Noiseless Hitch Weight with Roller, \$3.00 extra.

CAST IRON MANGER WITH WROUGHT IRON HAY RACK FOR BOX STALL.



No. 57G.

Right hand.

Length on back, 4 feet ; length on side, 2 feet 6 inches.

Price each, \$23.00


Inside dimensions of Manger, 16x16x12 inches deep.

Noiseless Hitch Weight with Roller, \$3.00 extra.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

CORNER HAY RACK.

Cast Iron Top and Bottom, with Wrought Iron Rods.



No. 58G, 5 Bars, 1-2 inch Iron.

Projects from corner, 18 inches; height, 36 inches.
Price each, \$1.35

CORNER HAY RACK.

Cast Iron Top and Bottom, with Wrought Iron Rods.




No. 60G, 7 Bars, 5-8 inch Iron.

Projects from corner, 25 inches; height, 36 inches.
Price each, \$2.25

CORNER HAY RACK.

Cast Iron Top and Bottom, with Wrought Iron Rods.




No. 59G, 6 Bars, 5-8 inch Iron.

Projects from corner, 21 inches; height, 36 inches.
Price each, \$1.75

HALF CIRCLE HAY RACK.

Cast Iron Top and Bottom, with Wrought Iron Rods.




No. 61G

Width, 30 inches; projects from wall, 15 inches;
height, 36 inches. Price each, \$3.00

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.


Cast Iron Corner Hay Rack.



No. 62G.


Projects from corner, 24 inches ; height, 36 inches.
Price each, \$1.75.

Wrought Iron Corner Hay Rack.



- No. 63G, Projects from corner, 24 inches ; height, 31 inches. (For feeding from the floor.) Price each, - - - \$2.00
No. 64G, With rabbet to receive sheathing. (For feeding from the loft.) Price each, - - - 2.75


Wrought Iron Corner Hay Rack.



- No. 66G, Projects from corner, 24 inches ; height, 30 inches. (For feeding from the floor.) Price each, \$2.75
No. 67G, With rabbet to receive sheathing. (For feeding from the loft.) Price each, - - - 3.50

Heavy Wire Corner Hay Rack.

Used for Feeding from the Floor.




No. 65G.

Projects from corner, 24 inches ; height, 36 inches.
Price each, \$3.00.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.


Wrought Iron Corner Hay Rack.



- No. 68G, Projects from corner, 25 inches ; height, 30 inches. (For feeding from floor.) Price each, - - - \$3.75
- No. 69G, With rabbet to receive sheathing. (For feeding from above.) Price each, - - - 4.75

Extra Heavy Wrought Iron Corner Hay Rack.

Right or Left Hand.



RIGHT.

- No. 70G, Projects from corner, 20 inches ; height, 30 inches. (For feeding from floor.) Price each, - - - \$5.00
- No. 71G, With rabbet to receive sheathing. (For feeding from above.) Price each, - - - 6.00

Iron Wall Recess for Water Supply.



Size, 28 inches high ; 18 inches wide ; recess 5 1-2 inches deep.

The above is a neat arrangement for bringing the water supply into a flush recess in the wall of Stable or Washing room. It can be fitted with one or two faucets for hot or cold water. The trapped grating with cesspool below receives the waste water.

- No. 73G, Price of Wall Recess, with Trapped Cesspool, with Grating, less Faucets, - - - \$12.00
- Price of Nickel-Plated Faucets, each, - 1.50

CAST IRON COLLAR.




No. 72G.

- Length, 38 inches ; width, 18 inches. Price each, - - - \$1.40

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

WATER TROUGHS.


With Patent Overflow and Plug Strainer.



No. 74G, 16x16x10 inches deep,	-	-	-	-	\$ 3.90
" 75G, 20x14x12 " " "	-	-	-	-	4.70
" 76G, 20x16x12 " " "	-	-	-	-	5.30
" 77G, 24x20x12 " " "	-	-	-	-	6.10
" 78G, 30x20x12 " " "	-	-	-	-	9.50
" 79G, 36x16x12 " " "	-	-	-	-	11.00
" 80G, 36x21x15 " " "	-	-	-	-	12.00
" 81G, 48x16x12 " " "	-	-	-	-	12.50
" 82G, 48x20x15 " " "	-	-	-	-	13.50

Snow's Bell Water Inlet.

Can be fitted to any water trough.



No. 83G.

When you use this inlet on your trough there is no danger of the horse catching his harness. Much better than a faucet.

Price each, - - - \$2.00

HALF CIRCLE WATER TROUGH.


With Patent Overflow and Plug Strainer.



No. 84G, 25x14x12 inches deep, Price each,	-	-	-	-	\$ 5.25
No. 85G, 25x14x12 inches deep, with back, Price each,	-	-	-	-	7.00
No. 85½G, Enameled with back complete, Price each,	-	-	-	-	15.00


CORNER WATER TROUGH.

With Safety Overflow and Plug Outlet.



No. 86G, length on side, 17 inches ; depth, 12 inches ; Price each,	-	-	-	\$ 6.00
No. 87G, length on side, 24 inches ; depth, 12 inches ; Price each,	-	-	-	9.25
No. 88G, length on side, 36 inches ; depth, 16 inches ; Price each,	-	-	-	16.00

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.




IMPROVED WATER TROUGH.

With Patent Overflow and Plug Strainer.

Width, 19 inches ; Depth, 12 inches.

No. 89G,	36 inches long,	Plain Iron,	\$20.00
" 90G,	36 "	" Galvanized,	32.00
" 91G,	36 "	" Enameled,	33.00
" 92G,	48 "	" Plain Iron,	24.00
" 93G,	48 "	" Galvanized,	38.00
" 94G,	48 "	" Enameled,	42.00


The above troughs are furnished with pipe and Nickel-Plated Nozzle.



HALF CIRCLE WATER TROUGH.

With Patent Overflow and Plug Strainer.

No. 95G,	36x17x12 inches deep with Legs	
Plain Iron,	- - - -	\$10.50
No. 96G,	36x17x12 inches deep with Legs	
and Back Plain Iron,	- - -	14.00
No. 97G,	36x17x12 inches deep with Legs	
and Back Galvanized,	- - -	25.00
No. 98G,	36x17x12 inches deep with Legs	
and Back Enameled,	- - -	26.00
No. 99G,	40x20x12 inches deep with Legs	
Plain Iron,	- - - -	15.00
No. 100G,	40x20x12 inches deep with Legs	
and Back Plain Iron,	- - -	20.00
No. 101G,	40x20x12 inches deep with Legs	
and Back Galvanized,	- - -	33.00
No. 102G,	40x20x12 inches deep with Legs	
and Back Enameled,	- - -	34.00



WATER TROUGH FOR LIVERY STABLES.

With Safety Overflow and Plug Outlet.

No. 103G,	30x20x12 inches deep,	\$12.00
" 104G,	36x20x12 "	13.00
" 105G,	42x20x12 "	14.00
" 106G,	48x20x12 "	16.00

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

Always Use

The "Perfection" Buggy Washer

Pat. Mar '9, 1901.




2,500 in Daily Use.

It is a device for supporting the hose in such a manner that it can be carried around the vehicle in either direction with the minimum of Hose, Labor and Water. It keeps the hose hung up always off the floor, and gives free access for vehicles to be brought in or taken out of the wash-room.

The body is malleable iron and the hose arm galvanized wrought iron, 4 1/2 feet long (thus making a circle of 9 feet) and revolves on regular bicycle ball bearing joints, all threads are 3/4 inch iron pipe size, which is used the world over.

No. 107G, One Ball Bearing Joint, \$10.00
" 108G, Two Ball Bearing Joints, 12.00

Butt's Buggy Washing Device.




Pat. Dec. 10, 1889.

No. 109G, Price each, \$16.00

HARNESS WASHING SINKS.

With Safety Overflow and Plug Outlet.



Designed especially for Washing Harnesses.


A great convenience in the harness room. These sinks are made so you can wash the harness with ease and have no fear of splashing the water around. The sides catch all the water. The legs are very strong and it is made just the right height for a man to work easily. The Iron Back keeps the woodwork clean and free from water.

No. 110G,	36 in. long,	26 in. wide,	28 in. high,		\$12.00
" 111G,	36 " "	26 " "	28 " "	with Back,	15.00
" 112G,	48 " "	30 " "	28 " "		15.00
" 113G,	48 " "	30 " "	28 " "	with Back,	18.00
" 1134G,	36 " "			with back Enameled,	38.00

Every first-class stable should have one.

SMALL SIDE-WATER TROUGH.

With Brass Outlet Pipe.




No. 114G, 18x12x8 in. deep. Price each, \$2.75

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

BELL TRAP CESSPOOLS FOR DRAINING BOX STALLS AND WASHSTANDS.

CESSPOOL PLATES.


Or Drain Covers.



No. 115G, 6x6 inches, -	\$.30
" 116G, 7x7 " -	.35
" 117G, 8x8 " -	.40
" 118G, 9x9 " -	.50
" 119G, 10x10 " -	.60
" 120G, 12x12 " -	.75
" 121G, 14x14 " -	1.00
" 122G, 16x16 " -	1.50
" 123G, 18x18 " -	1.75

STRAINER.


To connect with 4-inch pipe.



No. 124G, 6x6 inches,
Price each, \$.60

SNOW'S SAFETY CESSPOOL.

With Bell Trap, for Asphalt, Granolithic or Wood Floors.



No. 125G.

Top 11 inches square, outlet 3 1/2 inches. Price each, \$4.50.


No. 125 1/2 G with Extra Long Spigot, \$6.50

Snow's Safety Cesspool you can always make tight, no more leaks around the edges. Especially designed for Asphalt, Granolithic or Wood Floors.

Special Brass Strainers and Cesspools to order at Short Notice.


EXTRA HEAVY CESSPOOL.

With Bell Trap and Double Grating for Draining Box Stalls and Washstands.




No. 126G, 12x12 inches -	\$3.00
127G, 16x16 " -	4.50

Showing section of Nos. 126G and 127G, Cesspool, with Double Grating and Bell Trap.




HEAVY CESSPOOL, With Bell Trap.




No. 128G, 6x6 inches, -	\$.75
" 129G, 9x9 " hinged, -	1.25
" 130G, 12x12 " not hinged, (light) -	2.00
" 131G, 12x12 inches, not hinged, (extra heavy) -	3.00

BELL TRAP CESSPOOLS, With Side Outlet.



No. 132G, 9x9 inches, hinged cover -	\$3.00
" 133G, 12x12 " not hinged cover -	4.50

CESSPOOLS WITH BELL TRAP, With Extra Long Spigot Outlets.



No. 134G, 9x9 inches hinged cover -	\$2.50
" 135G, 12x12 " not hinged cover -	4.00

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.


IRON MANURE SCUTTLE.

For Granolithic, Asphalt or Brick Floors.
With Solid Iron Cover.



No. 136G, 5 1/2 x 19 1/4 inches, Price each, - \$6.50

Section of 125G, Safety Cesspool



Showing Granolithic Setting with Inside
Caulked Connection.


STEEL MANURE SLIDE.



No. 137G, 18x20 inches, Price each, - \$8.00

Can be run by weight for counterbalance or
be caught at top while open by a spring catch.


IMPROVED MANURE SCUTTLE.



No. 138G,	15x16 inches,	Price each,	-	\$3.00
" 139G,	16x18	" " "	-	4.00
" 140G,	17x22	" " "	-	5.00

IRON MANURE SCUTTLE.

With Frame.



Diameter of opening, 14 inches.

No. 141G,	Scuttle, only,	Price each,	\$1.75
" 142G,	" with Frame,	" "	2.75

ACTUAL SIZE OF
GUTTERS.

143G.

145G.

147G.

146G.

Extra Large Outlet.

W. A. SNOW & CO.

CAULKED
WITH LEAD

SOIL
3
PIPE

LEAD

147 1-2G.

148G.

152G.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

STABLE GUTTERS.

With or Without Outlet.



Made 4 feet and 4 feet, 6 inches long.

No. 143G, width, 5 inches ; depth, $1\frac{1}{4}$ inches, - - - - - Price per foot, \$.25

STABLE GUTTER.

With Closed Ends.



No. 144G, made 4 feet and 4 feet, 6 inches long ; width, 5 inches ; depth, $1\frac{1}{4}$ inches, Price per foot \$.30

EXTRA HEAVY STABLE GUTTER.

With or Without Outlet.



No. 145G, made 4 feet and 4 feet, 6 inches long ; width $6\frac{1}{2}$ inches ; depth, $1\frac{1}{2}$ inches, Price per foot, \$.30

" 146G, same style and size as No. 145G, only made very heavy, - - - - - " " " .45

EXTRA DEEP GUTTER.

With or Without Outlet.



No. 147G, width, 8 inches ; depth, $2\frac{3}{4}$ inches, - - - - - Price per foot, \$.40

GRADED GUTTER.

(Medium Weight.)



Width, 6 1-2 inches ; graded from 1 1-2 to 4 1-2 inches.

No. 148G, Price of Gutter and Cover per foot, - - - - - \$1.30

" 149G, " " " per foot, - - - - - .80

" 150G, " " Cover, - - - - - .50

In ordering this Gutter, please state where Outlet is wanted, otherwise we shall place it in the centre of whole length.

Gutters of any shape or size made to order at short notice.

No. 145G and 147G Gutter made to order with extra large outlet to connect with 3-inch pipe if desired, shown in cut 147 1-2G on page 30.

HEAVY GRADED GUTTER AND COVER.

Angles and T pieces made for any of our Gutters when ordered.

With Cover. (Not Graded.)



Width, 8 inches ; depth 3 inches.

[illegible]

Extra Heavy.




Grades 1-8 inch to foot.

Width, 5 inches ; greatest depth, 5 inches.

[illegible]

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.




Showing Rear Covered Gutters with Leaders running into stalls.
Gutters Nos. 148G, 152G and 156G can be used in this way.

HEAVY GRADED GUTTER.

With Double Edge. Made Especially for Asphalt, Granolithic or Brick Floors.

GUTTER CESSPOOL.

With Bell Trap.



No. 159G.

Price each, - - - - \$5.00

Used with Gutters Nos. 148G, 152G, 153G, 156G and 160G.



The Double Edge holds the cement and prevents its chipping.

No. 160G, Gutter and Cover per foot,	-	-	-	\$1.75
" 161G, Gutter only, per foot,	-	-	-	1.20
" 162G, Cover only, per foot,	-	-	-	.55

Bell Trap Cesspools or common outlets made to connect with this Gutter at any desired point.

Angles and T pieces made for any of our Gutters when ordered.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.


HEAVY CAST IRON COW GUTTER.

With Flanges to Screw to Floor.



No. 163G,	11 in. wide,	3 in. deep,	inside measurement,	per foot,	\$1.00
" 164G,	14 " " "	3 " " "	" " " "	" " "	1.50
" 165G,	17 " " "	3 " " "	" " " "	" " "	1.75

HEAVY GRADED COW GUTTER AND COVER.




Width 15 inches; Graded from 2 to 6 inches, according to length.

No. 166G,	price of Gutter and Cover,	per foot,	- - - -	\$2.50
" 167G,	" " Gutter only,	- - - -	- - - -	2.00
" 168G,	" " Cover only,	- - - -	- - - -	1.00

NARROW STALL CHANNEL GUTTERS. (Graded.)



No. 169G,	5 feet long,	- - - -	Price each, \$.50
" 170G,	6 " "	- - - -	" " .80
" 171G,	7 " "	- - - -	" " 1.00
" 172G,	9 " "	- - - -	" " 1.50
" 173G,	12 " "	- - - -	" " 1.80



This cut shows a Stall Floor with Graded Channel Gutters, and No. 143G, or 144G and 145G, Rear Gutter.

Stall Floors arranged in this way can be made level, and are dry and healthy for the horse.

Be sure and use Clark's Elastic Cement, if you want tight floors, and do not want the urine to soak into the woodwork.


We have several patterns of Cow Gutters not listed, and will give special prices on application.

Cow Gutters made with round or square outlet, also made with hinged outlet when desired.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.


SNOW'S IRON CLAD STALL FLOOR.

OUR NUMBER
145G, 152G AND
153G GUTTERS
ARE RECOM-
MENDED TO BE
USED WITH
THESE FLOORS



VIEW OF IRON
CLAD FLOOR
WHERE
NUMBER 152G
COVERED
GUTTERS ARE
USED

SNOW'S IRON CLAD STALL FLOOR.



A good arrangement for a Stall Floor to be used in connection with an iron gutter in the rear of Stalls. The Stall Planks can easily be lifted and floor washed with hose or pail. Each floor is fitted with a Front Flange, to hold Planks in place without the use of screws.


Price List (Not including Plank Slats).

No. 174G, 5 feet,	6 inches by 2 feet,	5 inches,	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	\$12.00
" 175G, 6 "	1 " " 2 "	5 "	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	15.00
" 176G, 6 "	10 " " 2 "	4 "	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	18.00
" 177G, 6 "	10 " " 2 "	10 "	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	20.00
" 178G, 6 "	10 " " 3 "	4 "	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	23.00
" 179G, 8 "	0 " " 3 "	4 "	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	29.00

Special sizes made to order. These are all cast in one piece and made very heavy.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

WIRE STALL PARTITION GUARDS.



No. 180G.

No. 180G, O. G. Wire Stall Guard, with

ROUND END Stock Pattern,

3-16-inch wire, 6 feet long by 2 feet, 0 inches high,

Price each, \$3.25


All other sizes to order.

No. 182G. Price per square ft.,
3-16-inch wire, 2-inch mesh,

\$.35

No. 183G. Price per square ft.,
1-4-inch wire, 3-inch mesh,

\$.40



No. 181G.

No. 181G, O. G. Wire Stall Guard, with

SQUARE END Stock Pattern,

3-16-inch wire, 6 feet long by 2 feet, 0 inches high,

Price each, \$3.25


All other sizes to order.

No. 182½G. Price per square ft.,
3-16-inch wire, 2-inch mesh,

\$.35

No. 183½G. Price per square ft.,
1-4-inch wire, 3-inch mesh,

\$.40



No. 184G.


No. 184G. Price per square ft.,
3-16-inch wire, 2-inch mesh,

\$.35

No. 185G. Price per square ft.,
1-4-inch wire, 3-inch mesh,

\$.40

Sheet Steel Panels extra, according to the size required.



No. 186G with Steel Panel.

Wire Stall Partition Guard.

With Solid Sheet Steel Panel.

No. 186G, made of 3-16-inch wire. Price per square foot, \$.35

No. 187G, made of 1-4-inch wire. Price per square foot, \$.40

Sheet Steel Panels extra, according to the size required.

Any size made to order.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.



No. 188G.

We take pleasure in showing these stable fittings, used in the American Express Co.'s Stables, Boston.

No. 65G, Wire Hay Rack.

" 39G, Manger with Rolling Food Guard.

" 403G, Sliding Harness Hook.

" 189G, Steel Kicking Plates.

" 187G, Partition Guard, made of 1-4 wire.

For Fittings of above character we will furnish estimates on application.

STEEL KICKING PLATES.


No. 189G, curved to fit and screw on to posts. Usual size, 4 feet, 0 inches long by 2 feet, 6 inches high.

Price 50 cents per square foot.

Any size made to order.

Special prices on application.

WROUGHT IRON STALL GUARDS.



Height, 2 ft., 3 in.; 1/2-in. Round Iron.

No. 190G, length, 6 ft., 0 in., \$ 7.00

" 192G, " 7 " 0 " 8.50

" 194G, " 8 " 0 " 10.00

" 195G, " 8 " 6 " 10.75

" 196G, " 9 " 0 " 11.50

" 197G, " 9 " 6 " 12.25

Height, 2 ft., 3 in.; 5/8-in. Round Iron.

No. 198G, length, 6 ft., 0 in., \$ 9.00

" 200G, " 7 " 0 " 10.80

" 202G, " 8 " 0 " 12.60

" 203G, " 8 " 6 " 13.50

" 204G, " 9 " 0 " 14.40


" 205G, " 9 " 6 " 15.30

Guards made with 3-4 inch round iron at proportionate prices.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

WROUGHT IRON STALL GUARDS.

With Solid Sheet Steel Panels, 3 feet, 0 inches long.



Guards made with $\frac{3}{4}$ -inch Round Iron at proportionate prices.

Height, 2 feet, 3 inches; $\frac{1}{2}$ inch Round Iron.

No. 206G, length, 6 ft., 0 in., \$ 9.50

" 208G, " 7 " 0 " 11.00

" 210G, " 8 " 0 " 12.50

" 211G, " 8 " 6 " 13.25

" 212G, " 9 " 0 " 14.00

" 213G, " 9 " 6 " 14.75

Height, 2 feet, 3 inches; $\frac{5}{8}$ inch Round Iron.

No. 214G, length 6 ft., 0 in., \$11.50

" 216G, " 7 " 0 " 13.30

" 218G, " 8 " 0 " 15.10


" 219G, " 8 " 6 " 16.00

" 220G, " 9 " 0 " 16.90

" 221G, " 9 " 6 " 17.80

WROUGHT IRON BOX STALL GUARDS.

With Solid Sheet Steel Panels, 3 feet, 0 inches long.



Guards made with $\frac{3}{4}$ -inch Round Iron at proportionate prices.

Height, 2 feet, 3 inches.

$\frac{1}{2}$ -in. Round Iron.

No. 222G.

Price per lineal foot, \$1.25.


Height, 2 feet, 3 inches.

$\frac{5}{8}$ -in. Round Iron.

No. 223G.

Price per lineal foot, \$1.50

WROUGHT IRON BOX STALL GUARDS.



Guards made with $\frac{3}{4}$ -inch Round Iron at proportionate prices.

Height, 2 feet, 3 inches.

$\frac{1}{2}$ -in. Round Iron.

No. 224G.

Price per lineal foot, \$1.10.

Height, 2 feet, 3 inches.

$\frac{5}{8}$ -in. Round Iron.

No. 225G.

Price per lineal foot, \$1.40.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

WROUGHT IRON STALL GUARDS.

Cast Iron Ornaments. Solid Sheet Steel Panels, 3 feet, 0 inches long.



Guards made with $\frac{3}{4}$ -inch Round Iron at proportionate prices.

Height, 2 ft., 3 in., $\frac{1}{2}$ -inch Round Iron.


No. 226G, length, 7 ft., 0 in.,	\$12.00
" 227G, " 7 " 6 "	13.00
" 228G, " 8 " 0 "	14.00
" 229G, " 8 " 6 "	15.00
" 230G, " 9 " 0 "	16.00
" 231G, " 9 " 6 "	17.00

Height, 2 ft., 3 in., 5-8-inch Round Iron.

No. 232G, length, 7 ft., 0 in.,	\$13.00
" 233G, " 7 " 6 "	14.00
" 234G, " 8 " 0 "	15.00
" 235G, " 8 " 6 "	16.00
" 236G, " 9 " 0 "	17.00
" 237G, " 9 " 6 "	18.00

WROUGHT IRON BOX STALL GUARDS.

Cast Iron Ornaments. Solid Sheet Steel Panels, 3 feet, 0 inches long.



Guards made with $\frac{3}{4}$ -inch Round Iron at proportionate prices.

Height, 2 feet, 3 inches.

$\frac{1}{2}$ -in. Round Iron.

No. 238G.

Price per lineal foot, \$2.10.

Height, 2 feet, 3 inches.


5-8-in. Round Iron.

No. 239G.

Price per lineal foot, \$2.35.

WROUGHT IRON BOX STALL GUARDS.

Cast Iron Ornaments.



Guards made with $\frac{3}{4}$ -inch Round Iron at proportionate prices.

Height, 2 feet, 3 inches.

$\frac{1}{2}$ -in. Round Iron.

No. 240G.

Price per lineal foot, \$2.00.

Height, 2 feet, 3 inches.

5-8-in. Round Iron.


No. 241G.

Price per lineal foot, \$2.25.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.


EXTRA HEAVY WROUGHT IRON GUARDS.

With Cast Iron Ornaments. English Design.



No. 242G.

Prices on these English Stall Guards and other English goods will be given on application, and samples may be seen at our salesroom.




Flat Wrought Iron Stall Guards.

With T Iron Frame and Diamond Crimped Mesh; Riveted. **With Sheet Steel Panel Ends.**

Height, 2 feet, 3 inches.

No. 243G, length, 7 ft., 0 in.,	\$17.00
" 244G, " 7 " 6 "	18.00
" 245G, " 8 " 0 "	19.00
" 246G, " 8 " 6 "	20.00
" 247G, " 9 " 0 "	21.00
" 248G, " 9 " 6 "	22.00




Flat Wrought Iron Box Stall Guards.

With T Iron Frame and Diamond Crimped Mesh; Riveted.

No. 249G, height, 2 feet, 3 inches.
Price per lineal foot, \$2.00.

With Ornamental Border.

[illegible]

SECTION OF SINGLE STALL DIVISIONS.




This cut shows our No. 281G Post, with our No. 273G Brass Cap; No. 214G Guard, with Sheet Steel Panel; No. 263G Wall Post; No. 264G Heavy Cap Rail; and No. 267G Bottom Rail, whereby all the floor can be washed out and kept perfectly clean and no corners to clean out.


Special prices given on application for this outfit.

A black and white illustration of a wooden display case. The case has a glass top supported by several vertical wooden posts. The front of the case features a sign that reads "WASHOVI & CO". Below the sign are two large, dark rectangular panels, possibly doors or drawers. The entire case is enclosed within a simple rectangular frame.

Showing Full Guard on top of Door and method of fastening.





Grill with Woodwork all around it.



Wire Guard with wood all around it.

Made any length.



Section of Steel Cap-
ping No. 260G, for 1 3/4-
inch Wood Partition.

No. 260G, Straight, drilled for screws,		Price per foot, \$.25
" 261G, Curved, with rise of two feet,		" " " .35
" 262G, " " " " three feet,		" " " .40


THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

Wall or End Post.



No. 263G, Wall or End Post, total height, 6 ft., 10 in. Partition socket 4 ft., 6 in. high. Made for partitions that are $1\frac{3}{4}$ in. thick.

Any size made to order.
Price each, . . . \$3.50



No. 271G.

Wainscoting
Capping.

Price per ft.
\$.50

EXTRA HEAVY CAP RAIL.



Any length furnished to order.

No. 264G, Price per ft., with Groove to fit Wood Partition, $1\frac{3}{4}$ in. thick, \$.60
Furnished for any thickness of wood above $1\frac{3}{4}$ inches at extra cost.

BOTTOM OR WALL RAIL.

For Stall Partitions.



Any length furnished to order.

No. 265G, Price per ft., with Groove to fit Wood Partition, $1\frac{3}{4}$ in. thick, \$.45
Furnished for any thickness of wood above $1\frac{3}{4}$ inches at extra cost.

SNOW'S IMPROVED BOTTOM RAIL.

For holding the Partitions and preserving the wood work.

The rail setting up from the floor you have no corners to clean out and it allows you to wash out a series of stalls with a hose.



No. 288G. For Wood Floors.

Price per foot to fit $1\frac{3}{4}$ inch Wood Partition, \$.60




No. 267G. For Granolithic or Asphalt Floor.

Price per foot to fit $1\frac{3}{4}$ inch Wood Partition, \$.60

SECTION OF STALL CHANNEL.

With Round Corners. Full size.



No. 268G, Top Rail.
" 269G, Bottom Rail.
" 270G, Wall Rail.

Very strong and substantial.

Used for Top, Bottom or Wall Rail.

Made any length.

No. 268G, 269G, 270G, Price per lineal foot, \$.20
In ordering please order by number so we may know what it is to be used for.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.


POST CAPS IN IRON AND BRASS.



No. 272G. Price each, Iron, . \$1 50
" 273G. " " Brass, . 9.00




No. 274G. Price each, Iron, . \$ 1.75
" 275G. " " Brass, . 12.00




No. 276G. Price each, Brass, . \$15.00

IRON STALL POSTS FOR SINGLE AND BOX STALLS,


WITH IRON OR BRASS CAP.



Diameter of Post 5 in.
No. 277G, 6 feet high,
for Single Stalls, with
Iron Cap, . \$8.50
No. 278G, 7 ft., 4 in.,
high, for Box Stalls,
with Iron Cap, \$10.00
No. 279G, 6 feet high,
for Single Stalls, with
heavy Brass Cap, \$15.50
No. 280G, 7 ft., 4 in.,
high, for Box Stalls,
with heavy Brass Cap,
\$17.00



Diameter of Post 6 in.
No. 281G, 6 feet high,
for Single Stalls, with
Iron Cap, . \$9.50
No. 282G, 7 feet, 4
in. high, for Box Stalls,
with Iron Cap, \$11.00
No. 283G, 6 feet high,
for Single Stalls, with
heavy Brass Cap, \$18.00
No. 284G, 7 feet, 4 in.,
high, for Box Stalls,
with heavy Brass Cap,
\$19.50




Diameter of Post 6 in.
No. 285G, 6 feet high,
for Single Stalls, with
Iron Cap, . \$10.50
No. 286G, 7 feet, 4 in.,
high, for Box Stalls,
with Iron Cap, \$12.50
No. 287G, 6 feet high,
for Single Stalls, with
heavy Brass Cap, \$23.00
No. 288G, 7 feet, 4 in.,
high, for Box Stalls,
with heavy Brass Cap,
\$25.00



Ames Post.
Size, 6 inches by 2½
inches, with rounded
corner. Post and par-
titions come flush.

No. 289G, 6 feet high,
for Single Stalls, with
Iron Cap, . \$10.00
No. 290G, 7 ft. 4 in.,
high, for Box Stalls,
with Iron Cap, \$12.00
No. 291G, 6 feet high,
for Single Stalls, with
heavy Brass Cap, \$17.00
No. 292G, 7 ft. 4 in.,
high, for Box Stalls,
with heavy Brass Cap,
\$19.00



Diameter of Post, 6 in.
No. 293G, 6 ft. high,
for Single Stalls, with
Iron Cap, . \$10.50
No. 294G, 7 ft. 4 in.,
high, for Box Stalls,
with Iron Cap, \$12.50
No. 295G, 6 ft. high,
for Single Stalls, with
Brass Cap, . \$23.00
No. 296G, 7 ft. 4 in.,
high, for Box Stalls,
with Brass Cap, \$25.00

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.


**SELECTED
HARD PINE
STALL
POSTS.**



No. 297G.

6 inches diameter,
grooved 4 ft., 6 in.
high to take parti-
tion.

Price each, \$3.00




No. 298G

6 inches diameter,
grooved 4 ft., 6 in.
high to take parti-
tion.

Price each, \$4.00

IRON SOCKET.

Indispensable when wood posts are used,
which do not run to the ceiling.




Flanged to receive Wood Partitions.
No. 317G, 5 in. diam., Price each, \$1.25
" 318G, 6 " " " " 1.50
" 319G, 7 " " " " 2.00
" 320G, 8 " " " " 2.50

IRON POST SOCKET.

To be used with Brick or Granolithic.
No. 321G, 6 inches diameter, 12 inches
high, Price each, \$3.50

HITCH RING.




No. 299G, Japanned, \$.12
" 300G, extra heavy,
Japanned, .30
No. 301G, Galvanized, .15
" 302G, extra heavy,
Galvanized, .40
No. 303G, Brass, . 1.25

TIE RING.




No. 304G, Japanned, \$.12
" 305G, Galvanized, .15

**SWIVEL HITCH
RING.**




No. 307G, Japanned, \$.20
" 308G, Galvanized, .25


HITCH RINGS.




Polished Brass.
No. 309G, each, \$2.00




Polished Brass.
No. 310G, each, \$2.00




Polished Brass.
No. 311G, each, \$2.00



Polished Brass.
No. 312G, each, \$2.00




Polished Brass.
No. 313G, each, \$2.00



Polished Brass.
No. 314G, each, \$2.00


Any of our Hitch Rings can be made for round posts at
short notice.

Double Expansion Hitch Ring Bolt.




For Brick or Stone.
No. 315G, Iron, \$.60
" 316G, Pol-
ished Brass, 2.00

**A New and Improved Noiseless Hitching Arrangement
and Guard Box, with Leather Strap.**



Exterior View.



Interior View.

The weight always
takes up the slack,
whether the horse is
standing or lying
down.

The weight is cov-
ered with leather to
prevent noise when
in use.

Price each, complete
with Strap, \$4.00.


No Stall complete
without it.

No. 322G.


THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

VIEW OF TWO BOX STALLS WITH SLIDING DOORS.

Showing our Newport Post where the Doors Slide Through the Post.



ELEVATION



PLAN.

The door is hung on hangers from above, the track being concealed by the Iron Moulding.

The door slides through the center of the Post, saving much room and is taken entirely out of the way, with no possible chance for a horse to injure himself.

The front of the stall has a double partition enclosing the slide door so that no straw can clog its working and protects the horse when the door is pushed back.

The flush bolt in the door makes a secure fastening and cannot be opened by the horse in any way.

The Bumper Posts are made with inside rabbets to receive the doors when closed.

No. 324G, 8 feet, 6 inches high, for Box Stalls, with Iron Cap,	\$18.00
" 325G, 8 " 6 " " " " " " Heavy Brass Cap,	27.00


These Posts are used in all the best up to date stables.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

STALL WINDOW VENTILATOR.

With Sheet Steel Side Protectors.

Hinge the window at the bottom.




No. 326G.

This guard protects the window and also serves as a Ventilator—when the window is open no direct air comes on the horse.

Size, 30x24 inches high, . . . Price each, \$6.00
Made to fit any window at proportionate prices.

STALL WINDOW VENTILATOR.

With Sheet Steel Sides.




Hinging the window at the bottom you have an upward air draft and no direct air blows on the horse.

No. 327G, 30x24 inches high, with sides complete, \$6.00
" 328G, Frame, without Sheet Sides, . . . 3.00
Made to fit any window at proportionate prices.

STALL WINDOW VENTILATOR.

Without Steel Sides.




$\frac{1}{2}$ -inch Bars, 3-inch Centers.

No. 329G, 30x24 inches high, Price each, \$3.50
Made to fit any window at proportionate prices.


STALL WINDOW VENTILATOR.

With Sheet Steel Sides.



$\frac{1}{2}$ -inch Bars, 3-inch Centers.

No. 330G, 30x24 inches high, Price each, \$6.50
Made to fit any window at proportionate prices.


Stall Window Guard.

Made any size to order.


No. 331G, Price per sq. ft., \$.35
Hinges, extra, per pair, .50
Catch, extra, each, .40

Stall Ventilator.

With Adjustable Air Draft.




No. 332G, Price, glazed, \$2.00
Size, 9 1/2 x 16 inches.
No. 333G, Price, glazed, 4.00
Size, 16 x 21 inches.

Cast Iron Window Grating.

No. 334G, 12 x 15 inches, \$.75
" 335G, 12 x 18 " 1.00
" 336G, 12 x 19 " 1.25

Cast Iron Wheel Guard.

Extra Heavy.




Height, 16 inches.

No. 337G, Price per pair, 7 inches wide, \$1.50
No. 338G, Price per pair, 5 inches wide, 1.50

Wrought Iron Wheel Guard.

For Carriage House.




No. 339G.

Height, 2 feet.

Price per pair, 1-in. iron, \$3.00
Wrought Iron Wheel Guards
for Corner, made to order.
Prices on application.

Heavy Corner Door Fender.

Cast Iron.



No. 340G.

Height, 2 feet by 7 inches
inside, per pair, \$12.00

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

HARNESS ROOM FITTINGS.



No. 341G.

A special room for harnesses as generally arranged. But should a harness case be desired, it should be 8 feet high in the clear, with glass doors 5 feet, on centers.


ENGLISH VENTILATING HARNESS BRACKETS.

Frame Work of Japanned Iron, with Polished Mahogany Cappings.

SADDLE BRACKET.


BRIDLE BRACKET.

COLLAR BRACKET.



No. 342G.

Price each, \$2.50



No. 343G.

Price each, \$2.75




No. 344G.

Price each, \$2.75

CRUPPER BRACKET.

REIN BRACKET.



No. 345G.

Price each, \$.75

No. 347G, per set for Single Harness (5 pieces) \$ 9.50

" 348G, " " " Double " (10 pieces) 19.00




No. 346G.

Price each, \$.50

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

IMPROVED HARNESS BRACKETS.




This cut shows No. 349G Brackets with Harnesses placed on them.


Set 7 feet high and 21 inches on centers.

HARNESS BRACKETS.

A Great Convenience for the Harness Room.



No. 351G,	Price per set of five pieces,	\$1.25
" 352G,	" of Saddle Bracket Separate,	.35
" 353G,	" Collar " "	.30
" 354G,	" Hames " "	.25
" 355G,	" Bridle " "	.25
" 356G,	" Reins " "	.20




No. 349G.

Price each, \$1.00
Neat, compact and durable.

THE SPRAGUE HARNESS BRACKET.


Made entirely of wood and used in the best stables.
Keeps the Harness in a perfect condition.



Projects over all, 9 inches.

No. 350G, Price each, \$1.50

ENGLISH HARNESS BRACKETS.



Projects over all, 12 inches.


No. 357G, Price each, Japanned Iron, . . . \$2.50
" 358G, " " Vermilion, . . . 3.00

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

RIDING SADDLE BRACKETS.

GENTLEMEN'S SADDLE BRACKET.


Projects 17 inches.



No. 359G, Price, Japanned Iron, . . . \$2.50
 " 360G, " Vermilion, . . . 3.00

LADIES' SADDLE BRACKET.


Projects 20 inches.



No. 361G, Japanned Iron, . . . \$2.75
 " 362G, Vermilion, . . . 3.25

RIDING SADDLE BRACKET.


Projects 20 inches.



No. 363G.

Price with Mahogany Cappings, . . . \$5.00

RIDING SADDLE BRACKET.



No. 364G, Price each, Japanned, . . . \$1.50


Wrought Iron Bridle Bracket.

With Girth Hook.



No. 366G, Japanned, \$.70
 " 367G, Vermilion, .85


Bridle Bracket.



No. 368G, 4 ins. x 1 3/4 ins.

Price each, \$.25


RIDING BRIDLE BRACKET.



No. 365G.

Price with Mahogany Cap,
 \$1.25


GIRTH HOOKS.



No. 366 1/2 G.

Price per pair, Japanned,
 \$.50

STIRRUP BRACKET.



No. 367 1/2 G, Price Mahogany Cappings, . . . \$1.00

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

WASHING AND OILING HOOKS.

Adjustable Ceiling Bracket.

For Oiling and Washing.

Can be brought down to any required height and replaced above level when not in use.




No. 369G, Wrought Iron, \$6.00
No. 370G, Vermilion, 6.50

Washing Bracket.

With Ceiling Plate for

Leather Strap.




Complete with Strap.

No. 371G, Japanned Iron, \$2.50
No. 372G, Polished Brass, 5.00

Hook covered with leather, additional, \$1.50.

Adjustable Washing and Oil Harness Hook.




No. 373G.

No. 373G, Complete, with Grip, \$.90
Hooks Covered with Rubber when ordered.
No. 374G, Finished in Brass, \$2.50

Oiling Hook.




No. 375G, Japanned Iron, . . . \$.25
No. 376G, Brass, . . . 2.00
" 377G, Nickel Plated, . . . 3.00




No. 378G, Japanned Wrought Iron, \$1.25
No. 379G, Brass, . . . 3.50
" 380G, Nickel Plated, . . . 4.00

Whip Rack for Lash Whips.



Six Grooves.
No. 381G, Diameter 4½ inches.
Price each, . . . \$1.50

Whip Rack for Lash Whips.




Two Grooves.
No. 382G, Diameter 5 inches.
Price each, . . . \$1.00

Whip Rack for Lash and Straight Whips.



No. 383G, Price each, . . . \$.75

Whip Rack for Straight Whips.




No. 384G, five Whips, . . . \$.25
No. 385G, ten "50

Whip Rack for Straight Whips.



No. 386G, Price each, . . . \$.15

Bit Hook.




No. 387G, Brass, Price each, . . . \$.20


THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

WOOD HARNESS PINS.

With Japanned Iron Base,



No. 388G,	7½ inches,	per dozen,	Japanned Base,	\$1.25
" 389G,	9 "	" "	" "	1.50
" 390G,	12 "	" "	" "	2.00
" 391G,	15 "	" "	" "	2.50
" 392G,	18 "	" "	" "	3.75



Little Giant Hook.

Extra Heavy

No. 401G.

Length of Large Arm, 12 inches.

Length of Small Arm, 6 inches.

Price each, \$.50

Interchangeable Name Plate.



No. 404G,	Price each,	Japanned,	\$1.25
" 405G,	" "	Brass,	3.50

ENGLISH PILLAR ROPES.

With White Cord and Brass Snaps.



No. 406G,	3 feet long,	Price each,	\$2.50
-----------	--------------	-------------	--------

BACK CHAINS.




No. 407G,	Galvanized Chain and Snaps, each,	\$1.50
" 408G,	Brass Chain and Snaps, each,	9.00

MANILLA BACK ROPES.

With Snaps Attached.



No. 409G,	Manilla Rope, with Heavy Snaps, per foot,	\$.25
" 410G,	" " " " " and Rubber Covered, per foot,	.60



Snow's Adjustable Sliding Hook.

Arranged with large pulley and combination cleat.

For Brewery, Livery and Express Stables.


Length of Large Arm, 12 inches.

Length of Small Arm, 6 inches.

This Hook is placed on the posts at the rear of the Stalls and carries the harness up out of the way.


No. 393G,	5 inches, per dozen, Japanned,	\$ 1.00
No. 394G,	5 inches, per dozen, Brass,	12.00
No. 395G,	6 inches, per dozen, Japanned,	1.25
No. 396G,	6 inches, per dozen, Brass,	15.00
No. 397G,	8 inches, per dozen, Japanned,	1.50
No. 398G,	8 inches, per dozen, Brass,	18.00
No. 399G,	9 inches, per dozen, Japanned,	2.50
No. 400G,	8 inches, per dozen, Brass,	21.00

Heavy Harness Hook.



No. 402G.

Length of Large Arm, 10 inches,	Price each,	\$.40
---------------------------------	-------------	--------




No. 403G.

Price each, complete, with Pulley, Ropes and Cleat, \$2.50


THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

BLANKET BRACKETS.




No. 411G, per pair, 5-inch projection, Japanned Iron, \$	.40	No. 416G, per pair, 7-inch projection, Brass, .	\$3.00
" 412G, " " 7 " " " "	.50	" 417G, " " 9 " " " "	4.00
" 413G, " " 9 " " " "	.70	" 418G, tips for same, per pair, " "	2.00
" 414G, tips for same, per pair, " "	.30	" 419G, Hard Pine Pole, furnished any length,	
" 415G, per pair, 5-inch projection, Brass,	2.50	Price per foot, .12	

BLANKET BRACKETS.




No. 420G, per pair, projects 5 inches, Japanned Iron, .	.85
" 421G, " " " 5 " Brass, .	4.00
" 422G, 1 3/4 inches Hard Pine Pole for same, .	Price per foot, .12
" 423G, per pair, projects 7 1/2 inches, Japanned Iron, .	1.50
" 424G, " " " 7 1/2 " Brass, .	7.00
" 425G, 2 1/2 inch Hard Pine Pole for same, .	Price per foot, .30

SWINGING BLANKET BRACKET.



No. 426G, Price per pair, Japanned, .	\$ 3.00
" 427G, " " " Galvanized, .	6.00
" 428G, " " " Brass, .	15.00



No. 429G.

"Little Giant" Blanket Dryer
or Holder.


An article needed in every stable and
every house.

Price per pair, \$1.00

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

OVERHEAD SAFETY HITCH.


A Great Convenience for the Stable and Carriage House.



No. 430G,	Price complete with pulleys, ropes, cleats and snaps, Japanued,		\$1.25
" 431G,	" " Brass Mounted,		6.00

ENGLISH DOG CART STAND.

Strongly Made, with Adjustable Cross-Bar.



No. 432G, Price each, \$6.00



SHAFT SUPPORTER.

No. 433G.

Rubber Covered and Rubber
Tipped, \$1.00


A black and white illustration of five different types of hand tools hanging on a brick wall. From left to right: a large, flared metal bucket or shovel head; a smaller, rectangular metal shovel head; a pitchfork; a three-pronged garden fork; and a rectangular metal brush or comb head. Each tool has a long wooden handle and is mounted on the wall by a metal bracket. The tools are arranged in a row, with their handles extending downwards. The brick wall is depicted with a grid of horizontal and vertical lines, and the tools are mounted on a horizontal rail. The illustration is a detailed engraving, showing the texture of the metal and wood.

A pair of long, thin, curved surgical instruments, likely forceps, with a dark, textured surface. The instrument on the right has the text "W.A. SNOW & CO." engraved on its handle.A long, slender, dark-colored object, possibly a quill or a stylus, with a curved tip on the left and a small, light-colored mark near the right end.A detailed black and white illustration of a hanging lantern. The lantern features a glass chimney with a mesh screen inside, a metal frame, and a hanging hook at the top. It is shown attached to a wall bracket. The lantern has a decorative base and a small adjustment knob at the bottom.A black and white photograph of a wooden handle with a curved, forked end, likely a component of a traditional tool or weapon. The handle is dark and appears to be made of wood, with a smooth finish. The curved end is split into two prongs, resembling a pitchfork or a similar tool. The background is plain and light-colored.

No. 448G, Price each,
Japanned, \$.30

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

METHOD OF HANGING BUGGY SHAFTS.




No. 449G, Japanned, Rubber Covered, per pair,	.	.	.	.	\$2.25
" 450G, Brass, " " " "	.	.	.	.	8.00

Carriage Pole Bracket.

Crab Pole.



YOKE HANGING BRACKETS.



No. 451G, 1 Yoke Iron, per pair,	.	.	.	.	\$.75
" 452G, 1 " Brass, " "	.	.	.	.	2.50
" 453G, 2 " Iron, " "	.	.	.	.	1.50
" 454G, 2 " Brass, " "	.	.	.	.	5.50
" 455G, 3 " Iron, " "	.	.	.	.	2.00
" 456G, 3 " Brass, " "	.	.	.	.	8.00
" 457G, 4 " Iron, " "	.	.	.	.	2.50
" 458G, 4 " Brass, " "	.	.	.	.	10.50

Pole Bracket.

No. 459G, Japanned Iron,	\$1.00
" 460G, Brass or Bronze,	4.50
Additional if covered with Leather,	
\$1.00.	

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.


BUGGY SHAFT AND POLE BRACKETS.

POLE BRACKETS.



One Hook.

No. 461G, Japanned,
Price per pair, \$.50
No. 462G, Galvanized,
Price per pair, \$1.00
No. 463G, Brass,
Price per pair, \$4.00




Two Hook.

No. 464G, Japanned,
Price per pair, \$1.00
No. 465G, Galvanized,
Price per pair, \$2.00
No. 466G, Brass,
Price per pair, \$8.00



Three Hook.


No. 467G, Japanned,
Price per pair, \$1.50
No. 468G, Galvanized,
Price per pair, \$3.00
No. 469G, Brass,
Price per pair, \$12.00




Four Hook.

No. 470G, Japanned,
Price per pair, \$2.00
No. 471G, Galvanized,
Price per pair, \$4.00
No. 472G, Brass,
Price per pair, \$20.00


BUGGY SHAFT BRACKETS.




No. 473G.



No. 474G.




No. 475G.



No. 476G.

No. 473G, extreme projection, 3 inches, Japanned Iron,	.	.	.	.	.	.	.	.	.	Per pair, \$.50
" 474G, " " 6 " " "	.	.	.	.	.	.	.	.	.	" " .75
" 475G, " " 9 " " "	.	.	.	.	.	.	.	.	.	" " 1.00
" 476G, " " 12 " " "	.	.	.	.	.	.	.	.	.	" " 1.50
" 477G, " " 16 " " "	.	.	.	.	.	.	.	.	.	" " 2.00

Additional per pair if Rubber Covered, \$.30. Additional per pair if Leather covered, \$1.50.




Showing method of hanging Wagon Pole, with whiffletree, etc., on a set of five Brackets as above.

No. 478G, Price per set, with Rubber Covers as shown, Japanned Iron, \$ 3.50
" 479G, " " " " " " " " Brass, 12.00

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

Higbie Oats Cleaner.


Whitewood. Hard Oil Finish.



- No. 480G, Small stables, 1 to 15 Horses.
8½x15 inches, 6 feet 2 inches long,
Price each, \$25.00
No. 481G, Medium stables, 15 to 50
Horses. 11x16 inches, 6 feet 7
inches long.
Price each, 25.00
No. 482G, Large stables, 50 to 300
Horses. 14x16 inches, 6 feet 7
inches long.
Price each, 25.00

GRAIN CUT-OFF.

For Wall, when Wooden Shute is Used.



- No. 490G, Japanned Iron, \$.75
" 491G, Polished Brass, 3.00

Always Use the

HIGBIE OATS CLEANER


It is the Best
Made.

Galvanized Iron Grain Shute.



- No. 483G, 2 ½-inch, per foot, \$.11
" 484G, 4-inch, " " .15
" 485G, 5-inch, " " .20
" 486G, 6-inch, " " .25


GRAIN SLIDE.



- No. 492G, for 4-inch grain pipe,
Japanned Iron, \$1.00
No. 493G, for 5-inch grain pipe,
Japanned Iron, 1.50
No. 494G, for 6-inch grain pipe,
Japanned Iron, 2.00
No. 495G, for 4-inch grain pipe,
All Brass, 3.50
No. 496G, for 6-inch grain pipe,
All Brass, 7.00


Galvanized Iron Grain Shute with Hopper.

Hopper at top and protector at bottom to protect the horse from scratching himself. Indispensable where horses are fed from the loft above to connect with Manger. Cannot be chewed up, as the old wooden kind and much cheaper.



- No. 487G, Grain Shute, 2½ inches
diameter, with Hopper and Pro-
tector, 9 feet long. Price each
complete, \$1.50
No. 488G, Grain Hopper only,
for 2½-inch pipe. Price each, .35
No. 489G, Grain Hopper only,
for 4-inch pipe. Price each, .75

GRAIN SLIDE




- Made to connect with 5-inch Grain
Pipe.
No. 497G, Brass. Price each, \$10.00

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

CLARK'S TIME FEEDER FOR GRAIN.

Works while you sleep.


Allows the horse plenty of time to eat, before he works.



One clock and machine will feed from one to twenty horses, as desired.

No. 498G, Clock and Machine, each,	\$4.00
" 499G, Hopper for holding oats, each,	1.25

We very often arrange these Hoppers to be operated by hand. Prices given on application.




This cut shows Clark's Time Feeder when horses are fed from the loft and machine is down stairs.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

SALT DISH.


Cast Iron.



- No. 500G, 8x6x3 inches deep, Japanned, Price each, \$.60
 " 501G, 10x9x3 1/2 inches deep, Japanned, Price each, .80
 " 502G, 8x6x3 inches deep, Galvanized, Price each, 1.00
 " 503G, 10x9x3 1/2 inches deep, Galvanized, Price each, 1.40


SPONGE BOX.

Cast Iron.



- No. 504G, 14x6x6 inches deep, Japanned, Price each, \$1.00
 " 505G, 14x8x7 inches deep, Japanned, Price each, 1.20
 " 506G, 14x6x6 inches deep, Galvanized, Price each, 1.40
 " 507G, 14x8x7 inches deep, Galvanized, Price each, 1.60


SPONGE BOX.



- No. 508G, 22x7x7 inches deep, Japanned, Price each, \$ 2.50
 " 509G, 22x7x7 inches deep, Galvanized, Price each, 3.50
 " 510G, 22x7x7 inches deep, Brass, Price each, 20.00

Compressed Salt Bricks and Feeder.

For Horses, Cattle and Sheep.




Patented, November 1, 1892.

Do your horses always get Salt when wanted?

PURE SALT (Refined) acts as a tonic, invigorates the system, promotes digestion, purifies the blood, increases strength of bone and muscle; in fact, is a stimulus for the general health and thrift of animals, as well as of mankind.

- No. 511G, Feeder (for holding bricks) each, \$.50
 " 512G, Salt Bricks, each, .30

Wrought Iron Sponge Rack. English Design.




17 x 8 x 9 inches deep.

- No. 513G, Japanned, . . . \$2.50
 " 514G, Vermilion, . . . 3.00
 " 515G, Galvanized, . . . 3.50

WIRE SPONGE RACK.

Galvanized.



- No. 516G, 7 x 10, Galvanized Wire, . \$.75
 " 517G, 19 x 7 x 7, Galvanized Wire, . 1.75

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

CHAMOIS BRACKET.


Brass.



- No. 518G, length, 1 foot, 4 inches, projects 4 inches, . . . \$1.00
 No. 519G, length, 2 feet, 0 inches, projects 4 inches, . . . 1.50
 No. 520G, length, 2 feet, 6 inches, projects 4 inches, . . . 2.00

CHAMOIS WRINGER.


With Wrought Iron Swing Bracket.



- No. 521G, Chamois Wringer with Bracket, \$3.75
 " 522G, Chamois Wringer Bracket, . . . 2.25
 " 523G, Chamois Wringer, . . . 1.50


LARGE SOAP BOX.

With Strainer.



Length, 9 inches, width, 5 inches.


- No. 524G, Japanned, . . . \$1.00
 " 525G, Galvanized, . . . 1.50



CARRIAGE OR WAGON JACKS.

- No. 531G, Standard Size, \$1.00
 " 532G, Express Size, 1.50

HOSE BRACKET.



- No. 526G, Japanned, each, . . . \$.50

EXTRA HEAVY STABLE PAILS.


With Flush Bottoms.



- No. 527G, Pine, each, . . . \$.60
 " 528G, " Painted, each, . . . 1.10
 " 529G, Oak, each, . . . 1.00
 " 530G, " Painted, each, . . . 1.50
 Initials painted on same, extra,25

IMPROVED WAGON JACK.

Leather Cushioned.



- No. 534G, Carriage Size, each, . . . \$2.25
 " 535G, Livery Stable Size, each, . . . 2.75
 " 536G, For Wagons up to 8,000 lbs., each, 4.50

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

BOX STALL HINGES.


Be sure and send diameter of post with order.



With offset, 16 inches long from joint to end.


	Per pair
No. 537G, Malleable Iron, Japanned,	\$3.50
" 538G, Polished Brass,	9.00

This hinge allows the door to swing way back.




12 inches long from joint to end.

No. 539G, Wrought Iron, per pair,	\$6.50
" 540G, Polished Brass,	9.00




10 inches long from joint to end. Made to fit any size post.

No. 541G, Wrought Iron, per pair,	\$ 7.00
" 542G, Polished Brass, " "	10.00



Extra Heavy, 14 inches long from joint to end.

No. 543G, Wrought Iron, per pair,	\$ 9.00
" 544G, Polished Brass, " "	15.00




18 inches long from joint to end.

Made to fit any size post.

No. 545G, Wrought Iron per pair,	\$15.00
----------------------------------	---------

DOOR BOLT.



Length 8 inches x 2 inches wide.


No. 546G, Japanned,	\$1.00
" 547G, Brass,	4.50

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

Box Stall Door Mortise Bolt.

With Flush Handles.

Extra Heavy.




4 inches by 4 $\frac{3}{8}$ inches.

No. 548G, Price, Japanned,	.	.	.	\$3.50
" 549G, " Brass,	.	.	.	6.00

Box Stall Mortise Spring Latch.

With Flush Handles.

Extra Heavy.




4 $\frac{1}{4}$ inches by 4 $\frac{1}{4}$ inches.


No. 550G, Price, Japanned,	.	.	.	\$2.75
" 551G, " Polished Brass,	.	.	.	5.00

WROUGHT IRON SWINGING CRANES.

Made Heavy and Extra Heavy, in proportion to Weights Hoisted.



No. 552G.
Prices on application.




No. 553G.
Prices on application.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

STABLE SLIDING DOOR LOCKS, EXTRA HEAVY.

Made Expressly for the protection of the horses and to save them from injury, as the Latch Bolt is flush with the face.



No. 554G.


Operated from the outside by a key and in the inside by the Lift Lever.

No. 554G, price each, Japanned, \$3.00. Nickel Plated Bolt and Lift Lever. Two Nickel Plated Keys.

STABLE SLIDING DOOR LOCKS, EXTRA HEAVY.

For Stables and Fire-Houses.


With Concave face and Recessed Latch Bolt and Flush Cup and Drop Handles.



No. 555G, price each,
with Flush Cup and Drop
Handles, Japanned, \$ 5.00

No. 556G, price each,
with Flush Cup and Drop
Handles, Bronze Metal, 10.00

The concave face of the Lock contains the Latch Bolt which does not project beyond the face; the striker is convex to match the face of the Lock. All edges and corners are so rounded that there is no possibility of injury to the horse when passing through the doorway.




PROTECTION FOR HORSES.

The Latch Bolt is flush with the face; the strike catch is to be set back beyond the jamb of the door. With this lock, thus applied, there is no possibility of injury to the horse.



THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

BRASS GUARDS FOR FIRE DEPARTMENT HOUSES.



No. 557G.


Brass Sliding Poles, 2 inches outside diameter, per lineal foot, \$1.25.

Heavy Improved Flush Flanges for top and bottom of poles, \$4.00 each.

Heavy Brass Braces for top of poles, \$9.00 each.

FIRE DEPARTMENT HAY RACK.

Cast Iron Top and Bottom, with Wrought Iron Rods.




No. 558G.

Top projects from corner, 18 inches, height, 36 inches.

Bottom projects from corner, 9 inches.

Price each, \$1.75.

FIRE DEPARTMENT MANGERS.



No. 559G,	length,	24	inches,	width,	10	inches,	depth,	7	inches.	Price each,	\$2.00
" 560G,	"	17	"	"	9	"	"	7	"	"	1.75
" 561G,	"	17	"	"	7	"	"	7	"	"	1.75

Any of these sizes made detachable at an extra cost each of \$1.50; also the above sizes made with Rolling Food Guard to order at an extra cost each of 50 cents.

BOSTON ENGINE HOUSE TRACK.

Extra Heavy.



No. 562G.

Made Any Length to Order.

We make this track both smooth and raised, the smooth is used under the Engine. Price of each per lineal foot, \$1.00

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.




COW STABLE OF H. McKAY TWOMBLY, Madison, N. J.

Planned by Mr. Edward Burnett, 111 Fifth Avenue, New York

Fittings furnished by The W. A. Snow Iron Works.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.




COW STABLE OF HON. JOHN WANNAMAKER, Meadowbrook, Pa.

Planned by Mr. Edward Burnett, 111 Fifth Avenue, New York.

Fittings furnished by The W. A. Snow Iron Works.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.



COW STABLE OF HON. JOHN WANNAMAKER, Meadowbrook, Pa.

Planned by Mr. Edward Burnett, 111 Fifth Avenue, New York.

Fittings furnished by The W. A. Snow Iron Works.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.



COW STABLE OF F. W. VANDERBILT, Hyde Park, New York.

Fitted Complete With the "Burnett Cow Stalls" Complete as Shown on Page 72.

Planned by Mr. Edward Burnett, 111 Fifth Avenue, New York.

Fittings Furnished by The W. A. Snow Iron Works.


THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

"THE BURNETT" COW STALL.

The Best on Earth.

All steel construction giving the greatest cleanliness.

N
E
A
T
N
E
S
S



H
U
M
A
N
E

Patented December 30, 1902.


No. 563G.

View Showing Stall with Sliding Bar, Swivel Chain Hitch and Manger Cleanout.

We refer to cut on page 71 of F. W. Vanderbilt's Cow Stables which are fitted with the "Burnett Stalls" complete.

Prices given on application.

C
O
M
F
O
R
T




S
E
C
U
R
I
T
Y

Patented December 30, 1902.

No. 564G.

View Showing Section of Stall Partition and how they are anchored in the Granolithic.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.



Interior of Cow Stable of **H. McKay Twombly, Madison, N. J.** Planned by Mr. Edward Burnett, New York City. Fittings supplied by The W. A. Snow Iron Works.

No. 565G, Heavy Cow Ramps, as above. Price each, \$2.50

No. 566G, Light Cow Ramps, (same pattern.) Price each, \$1.50

No. 567G, Cow Gutter, 11 inches wide, 3 inches deep. Price per lineal foot, \$1.00

No. 568G, Cow Gutter, 14 inches wide, 3 inches deep. Price per lineal foot, \$1.50

Water in a stable is a necessity for the proper caring of the stock; it should be of suitable temperature, and the stock should have constant access to it.


The illustration opposite shows supply tank and connections, and the No. 569G Basins in position. The supply pipe is connected with the tank which is placed on a level with the basins, so the water rises to the same level as in the tank.

No. 570G, Basin is same style as No. 569G, except it has an improved flush bottom which enables it to be cleaned out more thoroughly and quickly.

No. 569G, Stanchion Basin, \$1.50
 " 570G, Improved " with flush bottom, 1.75

BUCKLEY PATENT WATERING DEVICE.

Water in a Stable a Necessity.



STANCHION BASIN.




No. 569G.

The above cut represents the regular Stanchion Basin, showing Valve, which is screwed on to the upright pipe inside of Basin.

This style is the same shape and size as No. 570G, and is made and put up in the same manner.

The Newton Tie Basin is same shape as for ordinary Stanchion, except that the back corners are concave, so as to allow bow to raise and lower and is also made to be put up same as No. 569G and No. 570G.

STANCHION BASIN.



No. 570G.

An examination of this cut shows its advantages over every other system. Can be emptied and cleaned in three minutes without fouling supply pipe in any way. Easily kept antiseptic.


The above cut represents the Improved Basin, showing bottom, which is flat with the Aluminum Valve so arranged that the water can be drawn from the Basin without its removal.

It is 12x14 inches across the top, 9 inches deep, weighs 20 pounds and holds from three to three and one-half gallons.

They are made to put up with locknut and washer or with the upright pipe to screw into the bottom as may be preferred.


THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

PRESCOTT'S PLAIN SWIVEL STANCHION.



No. 860G, Plain Swivel for Cows, each, \$1.50
 " 861G, " " Bulls, " 3.50

PRESCOTT'S IMPROVED SWINGING STANCHION.




No. 862G, Swinging Swivel for Cows, each, \$2.25

A Good Combination.

A Good Cow	}	Result: A Profitable Cow
A Clean Cow		
A Comfortable Cow		

SMITH'S SELF-ADJUSTING SWING CATTLE STANCHION.



Ease, Comfort and Thrift.

Most practical, useful, cheapest and best fastening invented.

Adjusts itself, when open, so that the animal cannot turn it when backing out, and locks itself when closed.

We claim this invention gives perfect freedom to cattle, in turning the head to either side, thus enabling them to lick the sides and shoulders, driving off flies, or lie down, resting the head upon the body as nature directs and requires.

That by using this fastening the cattle keep cleaner than by any other mode of fastening.

They cannot lie down in their droppings as when fastened with ropes or chains, cannot get caught by their head or horns in any way.

They are a perfectly safe fastening, and the cattle are quicker and easier fastened or unfastened than with ropes or chains.

They are strong and durable, and not liable to get out of order.

The Stanchions are made of hard wood timber, well oiled.

They turn on pivots in the center of the top and bottom. (The pivots are two-inch oak pins, furnished with stanchions.)


The upright, or side pieces, are 1½ or 2¼ inches, with edges rounded, the top and bottom, or cross pieces, are 3 by 4 inches. With the latch and clevis they are self-adjusting when being opened and closed.

Price each,

\$1.40

No. 574G, 6½-inch Neck Space for Cows, (Standard Size,) No. 575G, 5-inch Neck Space for Calves and Yearlings. No. 576G, 7-inch Neck Space for Steers. No. 577G, 8-inch Neck Space for Steers. No. 578G, 9-inch Neck Space for Oxen and Bulls.

Made any Desired Size or Shape.




A decorative rectangular panel featuring a grid pattern of dark, thick lines on a light background. The grid consists of 10 vertical and 10 horizontal lines, creating a 9x9 array of squares. At the top edge, there are three ornate fleur-de-lis ornaments, each centered over a vertical grid line. The entire panel is enclosed in a thin dark border.

A decorative border featuring a grid of squares with spiral motifs at the corners. The border is composed of a central grid of squares, with spiral motifs at the corners and along the edges. The grid is formed by dark lines on a light background, and the spiral motifs are also dark. The overall design is symmetrical and geometric.


A close-up photograph of a book cover or endpaper featuring a repeating geometric pattern. The pattern consists of dark, raised, diamond-shaped motifs arranged in a grid, creating a textured, three-dimensional effect. The background is a light, off-white color. The pattern is framed by a dark border.

Made of $\frac{1}{4}$ by $\frac{1}{8}$ -inch iron.	
No. 589G, $2\frac{1}{2}$ -inch mesh, per square foot,	\$.55
" 590G, $1\frac{1}{2}$ " " " " "	.75
This pattern made with larger sizes of iron at proportionate prices.	


Made of Iron and Brass.



No. 591G.



No. 592G.




No. 593G.


WIRE GUARDS FOR OFFICE RAILINGS, BANKS AND WINDOWS.



No. 594G.




No. 595G.



No. 596 G.

No. 594G, Diamond mesh pattern, 1 inch mesh, No. 12 Wire, per square foot,	.	.	.	.	\$.50
" 597G, " " " 1 1/2 " " " 10 " " " "	.	.	.	.	.40
" 598G, " " " 2 " " " 6 " " " "	.	.	.	.	.35
" 599G, " " " 3 " " " 4 " " " "	.	.	.	.	.35
Rosettes, per lineal foot extra, as shown in cut No. 595G,	.	.	.	.	.30
Pickets, " " " " " " " 595G,	.	.	.	.	.30

In ordering Wire Guards please send rough drawing specifying width and height.




Method of Framing Wire Work, as in No. 594G.

We make a large and varied assortment of Wire Work for Offices, Banks, Hotel and House Elevators, also for Store Windows and Doors, Window Guards, Gates, etc. Prices and estimates given on application.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

WOOD HITCHING POSTS.


Selected Chestnut, with Japanned or Galvanized Iron Caps.




Height, 3 feet, 8 inches
above ground.
Base, 2 feet, 6 inches.
No. 600G. Price each,
Japanned Cap, \$1.80
No. 601G. Price each,
Galvanized Cap, \$2.00



Height, 3 feet, 9 inches.
Base, 2 feet, 6 inches.
No. 602G. Price each,
Japanned Cap, \$2.00
No. 603G. Price each,
Galvanized Cap, \$2.30



With Galvanized Iron Cover.
Height above ground, 4
feet.
Base, 2 feet, 6 inches.
No. 604G. Price each,
Japanned Cap, \$2.50
No. 605G. Price each,
Galvanized Cap, \$2.75



With Galvanized Iron Cover.
Height above ground, 4
feet, 2 inches.
Base, 2 feet, 6 inches.
No. 606G. Price each,
Japanned Cap, \$3.10
No. 607G. Price each,
Galvanized Cap, \$3.60

IRON POST CAP,

For Wood Posts.



Hitching Bars, Galvanized Iron, with Snap to Attach to Posts.




No. 608G. Price all ready to attach to Post, . . . \$.50

No. 609G, 4 inches diameter, . . . \$.40
" 610G, 5 " "50
" 611G, 6 " "60

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

IRON HITCHING POSTS.

BALL TOP. HORSE HEAD. ROUND HEAD. RUSTIC. PLAIN HEAD.



Painted.
No. 612G.

To go in ground.

Price each, \$3.25

No. 613G.

To set in stone.

Price each, \$2.75



Painted.
No. 614G.

To go in ground.

Price each, \$6.50

No. 615G.

To set in stone.

Price each, \$5.00



Painted.
No. 616G.

To go in ground.

Price each, \$6.50

No. 617G.

To set in stone.

Price each, \$5.00



Painted.
No. 618G.

To go in ground.

Price each, \$6.00

Extra Heavy.




Painted.
No. 619G.

To go in ground.

Price each, \$7.00

WROUGHT IRON GRATING FOR SIDEWALKS AND AREAS.



No. 620G. Price per square foot,

Any size furnished to order.

\$1.00

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

MANHOLES, STREET CESSPOOLS AND GRATINGS.

CESSPOOL OR CISTERN COVER.


Checkered, with Rim.



- No. 621G, 20-inch Cover, 25-inch frame,
(heavy casting), \$3.50
No. 622G, 20-inch Cover, 25-inch frame,
(extra heavy casting), \$4.50
No. 623G, 24-inch Cover, 28-inch frame,
(extra heavy casting), \$6.50

CESSPOOL OR CISTERN COVER.


Plain, with Rim.



- | | | | |
|---|---|---|--------|
| No. 624G, 12-inch Cover, 15-inch frame, | . | . | \$1.25 |
| " 625G, 17-inch " 23-inch " | . | . | 1.75 |
| " 626G, 18-inch " 24-inch " | . | . | 2.25 |
| " 627G, 20-inch " 25-inch " (light casting) | . | . | 3.00 |
| " 628G, 20-inch " 25-inch " (heavy casting) | . | . | 3.50 |

EXTRA HEAVY SEWER MANHOLE COVER AND FRAME.

With Solid Top.




- No. 629G, diameter of Frame on top, 22
inches. Price each, \$9.00
No. 630G, diameter of Frame on top, 26
inches. Price each, \$14.00

- No. 631G, diameter of Frame on top, 26 inches.
Price each, \$16.00
Furnished with either Open or Closed Covers.

EXTRA HEAVY SEWER MANHOLE COVER AND FRAME.

With Open Top.



- No. 632G, diameter of Frame on Top, 26 inches, Price each, \$16.00
Furnished with either Open or Closed Covers.

We have on hand a large line of Cesspools, Manholes, etc., of different sizes and patterns, not illustrated in this catalogue. Manholes, Street Cesspools and Gratings for Cities and Towns a specialty with us.

Special designs made to order at short notice. Estimates and prices cheerfully given.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.


SEWER AND VAULT COVERS AND GRATINGS.



No. 827G,	8 inch,	price,	.	.	.	\$2.25
" 828G,	10 "	"	.	.	.	3.50
" 829G,	12 "	"	.	.	.	5.00
" 830G,	14 "	"	.	.	.	6.00
" 831G,	16 "	"	.	.	.	7.00
" 832G,	18 "	"	.	.	.	8.00

Square Cesspool or Cistern Cover.

Checkered with Rim.



No. 838G, 19 x 19 inches, price each, \$4.50

Round Grate and Frame.

For Cement or Brick.

Frame 3 inches deep.




No. 833G,	Grate 18 inches diameter,	price,	\$6.00
" 834G,	" 20 " " "	"	7.00
" 835G,	" 24 " " "	"	9.00

Square Grate and Frame.

For Cement or Brick.

Frame 3 inches deep.



No. 841G,	Plate 18 x 18 inches,	price,	\$ 7.50
" 842G,	" 20 x 20 " "	"	8.50
" 843G,	" 24 x 24 " "	"	10.00

Roadway Drain Grate and Frame.

Park Grate. Frame 3 inches deep.




No. 836G,	Grate 16 in. by 10 in.,	price,	\$5.00
" 837G,	" 22 " " 11 " "	"	6.50

Square Open Grate and Frame.

For Cement or Brick.


Frame 3 inches deep.



No. 844G,	Grate 18 x 18 inches,	price,	\$ 7.50
" 845G,	" 20 x 20 " "	"	8.50
" 846G,	" 24 x 24 " "	"	10.00

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

SPIRAL STAIRS.



No. 633G.

Estimates given on application.

We make all kinds of
Iron Work,
Folding Gates,
Entrance Gates,
Iron and Wire Fences,
Iron Balconies,
Iron Stairs,
Fire Escapes,
Iron Spiral Stairs.

Iron Grilles for Houses and Stores.

Estimates always cheerfully given.

FIRE ESCAPES.

As required by the Inspectors of the city of Boston, and the state of Massachusetts.

No. 634G.

Showing Balconies and Stairways.

Estimates on all kinds of Fire Escapes given on application.




Fire Escape.

With
 Folding
 Ladder.


No. 635G.

Estimates on all kinds of Fire Escapes given on application.



THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

 FIRE ESCAPE.



No. 855G.

Showing **Balconies** with **Stationary Stairs** and **Cantilever Stairs** at the bottom as required by the City of Boston.

FIRE ESCAPE.



No. 857G.

Showing **Balconies** and **Stationary Stairs** as erected for the City of Boston on Girls' High School, West Newton Street, Boston.



Competent men sent to take measurements. Estimates on all kinds of Fire Escapes given on application.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

COPPER WEATHER VANES.

A Compass given away with each.

ETHAN ALLEN.




Large, handsome, showy Horse Vane, at a low price.

No. 636G, Ethan Allen, size 31 inches, \$20.00
No. 637G, Ethan Allen and Wagon, size 42 in., \$40.00

The above cut represents Vane complete.


HACKNEY.

Full Bodied.




No. 638G, Hackney, 30 inches long, \$50.00
Mounted complete, with Spire Letters and Balls, same as No. 636G.

SMUGGLER (New Pattern).



No. 639G, Smuggler, 31 inches long, \$20.00
" 640G, " 42 " " 40.00
Mounted complete, with Spire, Letters and Balls, same as 636G.

BLACK HAWK.



No. 641G, Black Hawk, 27 inches long, \$15.00
" 642G, " " with Sulky and Driver, 30.00
Mounted complete, with Spire, Letters and Balls, same as No. 636G.


ALL OUR VANES ARE MADE OF COPPER AND GILDED WITH PURE GOLD LEAF.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.


COPPER WEATHER VANES.

A Compass given away with each.

PATCHEN.




ETHAN ALLEN, JR.




No. 646G, Ethan Allen, Jr., 25 inches long, . . . \$15.00
Mounted complete with Spire, Letters and Balls, same as
No. 643G.

MOUNTAIN BOY.



No. 647G, Mountain Boy, (New Design, full bodied),
size 33 inches, . . . \$35.00
Mounted complete, with Spire, Letters and Balls, same as
No. 643G.



No. 643G, Patchen, size 31 in., \$25.00
" 644G, " " 42 " 40.00
" 645G, " and Sulky,
size, 52 inches, . . . 60.00

 Above cut represents Vane
complete.

ALL OUR VANES ARE MADE OF COPPER AND GILDED WITH PURE GOLD LEAF.

A Compass given away with each.

Mounted complete, with Spire, Letters and Balls, same as No 643G.

A detailed black and white engraving of a horse in full gallop, facing right. The horse is depicted with flowing mane and tail, and its legs are extended in motion. It is standing on a simple horizontal base.

Mounted complete, with Spire, Letters and Balls, same as No. 643G.

Mounted complete, with Spire, Letters and Balls, same as No. 643G.


ALL OUR VANES ARE MADE OF COPPER AND GILDED WITH PURE GOLD LEAF.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

COPPER WEATHER VANES.


A Compass given away with each.

NANCY HANKS, (with Pneumatic Tire Sulky).




No. 658G, 31 inches long, including Sulky and Driver,	\$50.00
" 659G, painted in colors,	60.00
Mounted complete, with Spire, Letters and Balls, same as No. 643G.	

DEXTER AND JOCKEY.



No. 660G, Dexter and Jockey, size 32 inches,	\$30.00
" 661G, " " Sulky,	40.00
" 662G, " " Wagon,	50.00
Mounted complete, with Spire, Letters and Balls, same as No. 643G.	

GOLDSMITH MAID.



No. 663G, Goldsmith Maid, 42 inches long,	\$40.00
Mounted complete, with Spire, Letters and Balls, same as No. 643G.	

ALL OUR VANES ARE MADE OF COPPER AND GILDED WITH PURE GOLD LEAF.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

COPPER WEATHER VANES.

A Compass given away with each.


HAMBLETONIAN.




No. 664G, Hambletonian, (New Design), 20x30 inches, \$25.00
Mounted complete, with Spire, Letters and Balls, same as No. 643G.

MERINO RAM.

SHEEP.



No. 665G, Sheep, 28 inches long, \$25.00
" 666G, " 30 " " 30.00
" 667G, " Full Bodied, 34
inches long, 50.00
Mounted complete, with Spire, Letters
and Balls, same as No. 643G.



No. 668G, Ram, 28 inches long, \$30.00
" 669G, " 30 " " 40.00
" 670G, " 34 " " 50.00
Mounted complete, with Spire, Letters and Balls, same
as No. 643G.

ALL OUR VANES ARE MADE OF COPPER AND GILDED WITH PURE GOLD LEAF.


THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

COPPER WEATHER VANES.

A Compass given away with each.

BANNERET.

Any size to order.




No. 671G, 2 1/2 feet long,	\$20.00
" 672G, 3 " "	30.00
" 673G, 3 1/2 " "	40.00
" 674G, 4 " "	50.00

Mounted complete with Spire, Letters and Balls, same as no 675G.

INITIAL BANNERET.

Any size to order.



No. 679G, 2 1/2 feet long,	\$20.00
" 680G, 3 " "	30.00
" 681G, 3 1/2 " "	40.00
" 682G, 4 " "	50.00

Mounted complete, with Spire, Letters and Balls, same as No. 675G.

LEADER BANNERET.

Any size to order.


No. 675G, 2 1/2 ft. long, \$20.00

No. 676G, 3 ft. long, \$30.00

No. 677G, 3 1/2 ft. long, \$40.00

No. 678G, 4 ft. long, \$50.00

Mounted complete with Spire, Letters and Balls.



BANNERET.

Any style to order.


No. 683G, 2 1/2 ft. long, \$20.00

No. 684G, 3 ft. long, \$30.00

No. 685G, 3 1/2 ft. long, \$40.00

No. 686G, 4 ft. long, \$50.00

Mounted complete with Spire, Letters and Balls, same as No. 675G.




ALL OUR VANES ARE MADE OF COPPER AND GILDED WITH PURE GOLD LEAF.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

COPPER WEATHER VANES.

A Compass given away with each.

EASTLAKE BANNERET.




Any style made to order.

No. 687G, 2 feet long,	. . .	\$15.00
" 688G, 2 1/2 " "	. . .	20.00
" 689G, 3 " "	. . .	30.00
" 690G, 4 " "	. . .	40.00

Mounted complete, with Spire, Letters and Balls, same as No. 675G.


BANNERET. (New Design).



No. 691G, 2 feet long,	. . .	\$15.00
" 692G, 2 1/2 " "	. . .	20.00
" 693G, 3 " "	. . .	30.00
" 694G, 3 1/2 " "	. . .	40.00

Mounted complete, with Spire, Letters and Balls, same as No. 675G.

BANNERET. (New Design).




Any Style to order.

No. 695G, 2 1/2 feet long,	. . .	\$20.00
" 696G, 3 " "	. . .	30.00
" 697G, 3 1/2 " "	. . .	40.00
" 698G, 4 " "	. . .	50.00

Mounted complete, with Spire, Letters and Balls, same as No. 675G.

BANNERET.



Any size made to order.


No. 699G, 2 feet long,	. . .	\$15.00
" 700G, 2 1/2 " "	. . .	20.00
" 701G, 3 " "	. . .	30.00

Mounted complete, with Spire, Letters and Balls, same as No. 675G.

ALL OUR VANES ARE MADE OF COPPER AND GILDED WITH PURE GOLD LEAF.

A Compass given away with each.

BANNERET. (New Design.)



No. 702G, 2 feet long,	\$15.00
" 703G, 2 1/2 " "	20.00
" 704G, 3 " "	30.00
" 705G, 3 1/2 " "	40.00

Mounted complete, with Spire, Letters and Balls, same as No. 675G.

No. 706G, Grecian Sparkler, 5 feet long,

This is a new and attractive Vane. The fan being covered with Isinglass, makes a very showy appearance while revolving in the wind.

Mounted complete, with Spire, Letters and Balls, same as No. 675G.


ALL OUR VANES ARE MADE OF COPPER AND GILDED WITH PURE GOLD LEAF.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

COPPER WEATHER VANES.

A Compass given away with each.

ROMAN SCROLL.




Any size made to order.

No. 707G, Roman Scroll, 5 feet long,

\$40.00

Mounted complete, with Spire, Letters and Balls, same as No. 675G.

GRECIAN SCROLL.



Any size made to order.

No. 708G, 3 feet long,

\$17.00

" 709G, 4 " "

22.00

" 710G, 5 " "

40.00

" 711G, 6 " "


70.00

Mounted complete, with Spire, Letters and Balls, same as No. 675G.

ALL OUR VANES ARE MADE OF COPPER AND GILDED WITH PURE GOLD LEAF.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.


CHURCH OR SCROLL VANE.



No. 712G, 4 1/2 feet,	\$40.00
" 713G, 5 "	50.00
" 714G, 5 1/2 "	60.00
" 715G, 8 "	85.00

Mounted complete, with Spire, Letters and Balls, same as No. 675G.


CHURCH OR SCROLL VANE.



No. 716G, 12 inches,	\$ 5.00
" 717G, 15 "	6.00
" 718G, 18 "	8.00
" 719G, 2 feet,	10.00
" 720G, 2 1/2 "	12.00
" 721G, 3 "	16.00
" 722G, 3 1/2 "	18.00
" 723G, 4 "	25.00
" 724G, 4 1/2 "	40.00
" 725G, 5 "	45.00
" 726G, 5 1/2 "	50.00
" 727G, 6 "	65.00
" 728G, 8 "	80.00
" 729G, 10 "	100.00
" 730G, 12 "	125.00

Mounted complete, with Spire, Letters and Balls, same as No. 675G.

ARROW.



No. 731G, 12 inches,	\$ 4.00
" 732G, 15 "	5.00
" 733G, 18 "	6.00
" 734G, 24 "	8.00
" 735G, 30 "	10.00
" 736G, 36 "	13.00
" 737G, 42 "	16.00
" 738G, 48 "	20.00
" 739G, 60 "	30.00

Mounted complete, with Spire, Letters and Balls, same as No. 675G.

PEN.



No. 740G, 24 inches long,	\$12.00
" 741G, 36 "	16.00
" 742G, 48 "	22.00
" 743G, 60 "	40.00
" 744G, 72 "	55.00


Mounted complete, with Spire, Letters and Balls, same as No. 675G.

ALL OUR VANES ARE MADE OF COPPER AND GILDED WITH PURE GOLD LEAF.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

COPPER WEATHER VANES.

A compass given away with each.




EAGLES.

We make a Perfect Eagle, wholly of Copper, with double thick wings. Arrows are indispensable when Eagles are used as Vanes. Eagles with Arrows, Spires, Letters and Balls complete.

No. 745G, 1 foot, 3 inches spread,	\$ 20.00
" 746G, 1 " 6 " "	25.00
" 747G, 2 feet spread,	35.00
" 748G, 2 " 6 inches spread,	50.00
" 749G, 3 " spread,	60.00
" 750G, 3 " 6 inches spread,	70.00
" 751G, 4 " spread,	85.00
" 752G, 4 " 6 inches spread,	115.00
" 753G, 5 " spread,	135.00
" 754G, 5 " 6 inches spread,	150.00
" 755G, 6 " 6 " "	175.00
" 756G, 7 " spread,	215.00
" 757G, 8 " " "	250.00
" 758G, 10 " " "	325.00

Mounted complete with Spire, Letters and Balls, same as No. 675G.

EAGLES.




No. 759G, 15 inches spread,	\$ 20.00
" 760G, 18 " "	25.00
" 761G, 25 " "	35.00
" 762G, 31 " "	50.00
" 763G, 54 " "	100.00
" 764G, 66 " "	125.00

Mounted complete, with Spire, Letters and Balls, same as No. 675G.

Copper Balls on Stem.

Gilded with Gold Leaf, for Flag Staff.



No. 765G, 3 inch,	\$.70
" 766G, 4 " "	1.10
" 767G, 5 " "	1.40
" 768G, 6 " "	2.00
" 769G, 7 " "	3.00
" 770G, 8 " "	3.50
" 771G, 10 " "	7.75
" 772G, 12 " "	12.00

ALL OUR VANES ARE MADE OF COPPER AND GILDED WITH PURE GOLD LEAF.

A Compass given away with each.


OXEN.



(Full Bodied) 50.00

Mounted complete, with Spire, Letters and Balls, same as No. 675G.

COW.



Mounted complete, with Spire, Letters and Balls, same as No. 675G.

STEAM FIRE ENGINE VANE.



Mounted complete, with Spire, Letters and Balls, same as No. 675G. Smaller sizes of Fire Engines made at proportionate prices. 250.00

ALL OUR VANES ARE MADE OF COPPER AND GILDED WITH PURE GOLD LEAF.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

COPPER WEATHER VANES.


A Compass given away with each.

WYANDOTTE. (New Pattern).



No. 783G, Wyandotte, 19x24 inches, \$20.00
Mounted complete, with Spire, Letters and Balls, same as No. 675G.

GAME COCK WITH ARROW.




No. 784G, Game Cock, 16 inches high, \$12.00
" 785G, " " 24 " " 24.00
Mounted complete, with Spire, Letters and Balls, same as No. 675G.

ROOSTERS.



No. 786G, Rooster, (Full Bodied) 18 inches high, \$20.00
" 787G, " " 31 " 40.00
Mounted complete, with Spire, Letters and Balls, same as
No. 675G.

ROOSTERS.



No. 788G, Rooster, small, 12x12 inches, \$ 7.00
" 789G, " medium, 19x24 inches, 15.00
Mounted complete, with Spire, Letters and Balls, same as
No. 675G.

GAME COCK.



No. 790G, Game Cock, 16 inches high, \$10.00
" 791G, " " 24 " " 20.00
" 792G, " " 28 " " 30.00
Mounted complete, with Spire, Letters and Balls, same as
No. 675G.

ALL OUR VANES ARE MADE OF COPPER AND GILDED WITH PURE GOLD LEAF.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

COPPER WEATHER VANES.

A compass given away with each.

DEER.




- No. 793G, Deer, 31 inches long, without bush, . . . \$35.00
 " 794G, " 31 " " with bush, . . . 40.00
 Mounted complete, with Spire, Letters and Balls, same as No. 675G.

STORK.



- No. 795G, Stork, 24 inches high, . . . \$25.00
 Mounted complete, with Spire, Letters and Balls, same as No. 675G.

FISH.




- No. 796G, Codfish, 31 inches, . . . \$22.00
 " 797G, " 48 " " . . . 35.00
 " 798G, Pickerel, 36 " " . . . 25.00
 " 799G, " 48 " " . . . 35.00
 Any other size made to order.
 Mounted complete, with Spire, Letters and Balls, same as No. 675G.

MASSASOIT.




- No. 800G, Massasoit, 30 inches high, . . . \$40.00
 Mounted complete, with Spire, Letters and Balls, same as No. 675G.

DOG.



- No. 801G, Dog, 34 inches long, . . . \$25.00
 Mounted complete, with Spire, Letters and Balls, same as No. 675G.

VESSELS.



- No. 802G, Yacht, Sloop rigged, 30 inches, . . . \$ 40.00
 " 803G, " Schooner " 30 " " . . . 50.00
 " 804G, " Sloop " 40 " " . . . 50.00
 " 805G, " Schooner " 40 " " . . . 60.00
 " 806G, " Sloop " 50 " " . . . 75.00
 " 807G, " Schooner " 50 " " . . . 100.00
 " 808G, Clipper Ship " 30 " " . . . 50.00
 " 809G, " " " 36 " " . . . 65.00
 " 810G, " " " 50 " " . . . 100.00
 Mounted complete, with Spire, Letters and Balls, same as No. 675G.

ALL OUR VANES ARE MADE OF COPPER AND GILDED WITH PURE GOLD LEAF.

THE W. A. SNOW IRON WORKS, 19 PORTLAND STREET, BOSTON.

COPPER FINIALS. WITH JACKETS.

Ornaments Gilded.

In ordering be sure and Send Detail Drawing showing Pitch of Roof, also state whether the tower is Square, Round, Hexagon or Octagon.




No. 811G.

Total height over all,
4 feet, 6 inches.
Price each, . \$7.50



No. 812G.

Total height over all,
4 feet, 6 inches.
Price each, . \$9.50




No. 813G.

Total height over all,
4 feet.
Price each, . \$11.00




No. 814G.

Total height over all,
5 feet.
Price each, . \$15.00




W. A. SNOW & CO
No. 815G.

3 feet high.
Price each, . \$14.00




No. 816G.

Total height over all,
3 feet, 6 inches.
Price each, . \$7.00



No. 817G.

Total height over all,
4 feet.
Price each, . \$16.00



No. 818G.

Total height over all,
3 feet, 3 inches.
Price each, . \$7.00

In ordering be sure and Send Detail Drawing showing Pitch of Roof, also state whether the tower is Square, Round, Hexagon or Octagon.

ALL KINDS OF COPPER FINIALS MADE TO ORDER.

COPPER FINIALS, WITH JACKETS.

Ornaments Gilded.


In ordering be sure and send detail drawing showing Pitch of Roof, also state whether the tower is square, round, hexagon or octagon.



W.A. SNOW & CO.

No. 819G.

5 feet high. Price each, \$18.00



No. 820G.

5 feet high.

Price each, . . . \$14.00




W.A. SNOW & CO.

No. 821G.

4 feet high.

Price each, . . . \$14.00



W.A. SNOW & CO.

No. 822G.


4 feet high.

Price each, . . . \$12.00



No. 823G.

5 feet high. Price each, \$12.00




W.A. SNOW & CO.

No. 824G.

2 feet high.

Price each, . . . \$12.00



W.A. SNOW & CO.

No. 825G.

2½ feet high.

Price each, . . . \$14.00



No. 826G.

5 feet high.

Price each, . . . \$15.00

In ordering be sure and send detail drawing showing Pitch of Roof, also state whether the tower is square, round, hexagon or octagon.

ALL KINDS OF COPPER FINIALS MADE TO ORDER.

INDEX

	PAGE
Back Tie Ropes.....	54
Bit Hooks.....	53
Blanket Brackets.....	55
Blanket Dryers.....	55
Bottom Rails.....	43
Box Stall Hinges.....	64
Box Stall Locks.....	65
Box Stall Posts.....	44-47
Bridle Brackets.....	52
Broom Holders.....	57
Buckley's Cow Watering Device.....	74
Buggy Washing Devices.....	27
Buggy Shaft Brackets.....	58, 59
Bell Outlets.....	25
Capping for Partitions.....	42, 43
Carriage Guards.....	49
Carriage Jacks.....	63
Cesspools.....	28
Cesspool Plates.....	28
Chamois Brackets.....	63
Chamois Wringer.....	63
Cistern Covers.....	80, 81
Cleaning Hooks.....	53
Clock Feeders.....	61
Collars, Cast Iron.....	24
Copper Finials.....	96, 97
Cow Gutters.....	34
Cow Stanchions.....	74, 75
Cow Stalls.....	68-73
Cow Water Device.....	74
Cranes.....	65
Dog Cart Stand.....	56
Door Bolts.....	64
Door Fenders.....	49
Door Guards.....	42
Drain Covers.....	28-80-81
Engine House Tracks.....	67
Feed Pipe.....	17-18-60
Finials.....	96, 97
Fire Department Fittings.....	67
Fire Department Hay Racks.....	67
Fire Department Mangers.....	67
Fire Escapes.....	81, 82
Flagstaff Balls.....	92
Girth Hooks.....	52
Grain Cut-Off.....	60
Grain Shutes.....	60
Grain Slides.....	60
Grilles.....	76, 77
Gutters.....	30-34
Harness Brackets.....	50, 51, 52
Harness Hooks.....	54
Harness Pins.....	54
Harness Washing Sink.....	27
Hay Racks.....	20-24
Hinges.....	64
Hitching Bars.....	78
Hitching Posts, Wood.....	78
Hitching Posts, Iron.....	79
Hitch Rings.....	45
Hitching Weights.....	57
Hoof Cleaners.....	57
Hose Brackets.....	63
Implement Hooks.....	57
Iron Cranes.....	65
Iron Grilles.....	76, 77
Iron Stairs.....	81, 82
Kicking Plates.....	37
Lantern Brackets.....	57

	PAGE
Locks.....	65, 66
Mangers.....	17-21
Manhole Frames and Covers.....	80, 81
Manure Scuttles.....	29
Manure Slides.....	29
Name Plates.....	54
Oat Cleaners.....	60
Office Railings.....	76, 77
Oiling Hooks.....	53
Overhead Hitches.....	56
Pails.....	63
Partition Guards.....	36-42
Pig Troughs.....	73
Pillar Chains.....	54
Pillar Ropes.....	54
Pole Brackets.....	58, 59
Post Caps.....	44, 78
Post Sockets.....	45
Posts, Iron.....	44-47
Riding Saddle Brackets.....	52
Robe Brackets.....	55
Safety Hitches.....	56
Salt Bricks and Feeders.....	62
Salt Dishes.....	62
Sewer Manhole Frames and Covers.....	80, 81
Shaft Brackets.....	58
Shaft Supporters.....	56
Sidewalk Gratings.....	79
Sliding Harness Hooks.....	54
Sliding Poles.....	67
Soap Box.....	63
Spiral Stairs.....	81
Sponge Boxes.....	62
Stable Pails.....	63
Stable Fork, Wood.....	57
Stairs, Iron.....	81
Stall Cleaners.....	57
Stall Floors, Snow's Sanitary.....	4-16
Stall Floors, Snow's Iron Clad.....	35
Stall Guards.....	36-42
Stall Posts, (Iron).....	44-47
Stall Posts, (Wood).....	45
Stall Window Guards.....	48, 49
Stirrup Brackets.....	52
Steel Kicking Plates.....	37
Street Manhole.....	80, 81
Tie Rings.....	45
Time Feeders.....	61
Top Rails.....	43
Ventilators.....	48, 49
Vanes.....	82-95
Wagon Jacks.....	63
Wall Posts.....	43
Wall Rails.....	43
Water Recess.....	24
Wall Sockets.....	43
Washing Hooks.....	53
Water Troughs.....	25-27
Weather Vanes.....	82-95
Wheel Guards.....	49
Whip Racks.....	53
Window Gratings.....	48, 49-77
Window Guards.....	48, 49-77
Wire Railings.....	77
Wood Stall Posts.....	45
Wood Stable Forks.....	57
Yoke Brackets.....	58

